

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-063-20,604

LEASE NAME Jacobs

WELL NUMBER "M" #1

SPOT LOCATION SE SW SW

SEC. 20 TWP 14 RGE 27

COUNTY Gove

Date Well Completed _____

Plugging Commenced 5-3-85

Plugging Completed 5-13-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pickrell Drilling Company

ADDRESS 110 N. Market, Suite 205, Wichita, Ks. 67202

PHONE # (316)-793-5742 OPERATORS LICENSE NO. 5123

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom T.D. 4350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	250'	None
				4-1/2"	4337'	1997.25'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from ___ feet to ___ feet each set.

Dumped 4 sacks cement on bottom, sanded back to 4,150 and dumped 4 sacks cement. Shot casing at 2500' and 2000'. Pulled 48 joints of 4-1/2" casing. Squeezed well with 3 sacks hulls, 26 sacks gel, 100 sacks cement, 7 sacks gel, 1 sack hulls, released plug and pumped 80 sacks of 50/50 pozmix cement with 6% added gel and 3% calcium chloride. Maximum pressure was 500 psi and shutting in 150 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Gt. Bend, Kansas 67530

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

MAY 15 1985
05-15-85
CONSERVATION DIVISION

James W. Rockhold (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says:
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 14th day of May, 1985

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton-County, Kansas
My Appt. Exp. 9-26-87

My Commission expires:

Iona M. Leatherman
Notary Public