

15-063-20021-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Location as "NE/CNW/SW" or footage from lines Gove County, Sec. 15-Twp. 14 Rge. 27 (E) (W) X  
C/NE/NW


Lease Owner Chief Drlg. Co., Inc.  
Lease Name R. Long Well No. 1  
Office Address 509 Century Plaza Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 10-13-71 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 11-5-71 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4405 Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	272	None
				5 1/2	4405	608.36'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.


Pushed a plug to 4250'. Dumped 25 ft. sand and 5 sacks cement. Shot pipe at 800, 700, and 600 ft. Pulled 19 jts. of 5 1/2" casing. Squeezed well with 5 sacks hulls, 25 sacks gel and 100 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 9 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Rockhold Engineering, Inc.  
Address Box 698 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss. James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold  
Box 698 Great Bend, Kansas 67530  
(Address)

Subscribed and sworn to before me this 8th day of November, 19 71

My commission expires September 30, 1975  
Cathy Miller Notary Public.

STENCILED

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU--KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

ORIGINAL

JUN 1 1968

15-063-20021-00-06  
SEC. 15 T. 14 R. 27W  
LOG. C NE NW

COMPANY GETTY OIL  
FARM R. Long NO. 1

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 4 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Gove  
KANSAS  
[Grid]

TOTAL DEPTH 4405'  
COMM. 1-3-68 COMP. 1-12-68  
SHOT OR TREATED  
CONTRACTOR Red Tiger Drlg.  
ISSUED 6-1-68

CASING  
20 10  
15 8 5/8" 272.74' cem w/ 225 sx  
12 6  
13 5 1/2" 4404' cem w/ 150 sx

ELEVATION 2518' KB  
PRODUCTION INJECTION  
Miss 4300-24

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale & Sand Streaks	0	272	TOPS: LOG	
Shale w/Shells	272	1271	Toronto	3703
Shale & Chalk	1271	1332	Lansing	3720
Shale & Shells	1332	1387	Kansas City	3899
Anhydrite (Blaine)	1387	1418	Fort Scott	4216
Shale & Shells	1418	1520	Mississippi	
Sand	1520	1740	Dolomite	4300
Shale & Shells	1740	1944	TD	4405
Anhydrite	1944	1985		
Shale & Shells	1985	2419		
Shale w/Lime	2419	3780		
Lime	3780	4405		

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*Maxne V. Starr*  
Maxne V. Starr

Subscribed and sworn to before me this 15th day of January, 1968.

*Betty M. Maloney*  
Notary Public

My Commission Expires:  
3-22-71