


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

County. Sec. 14 Twp. 14S Rge. 27S(E) (W)
Location as "NE/CNW&SW" or footage from lines. C SE NW
Lease Owner Tidewater Oil Company
Lease Name F. J. Rhoades Well No. 1
Office Address P.O. Box 157, Reece, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed April 22 1964
Application for plugging filed April 22 1964
Application for plugging approved April 22 1964
Plugging commenced April 22 1964
Plugging completed April 22 1964
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Depth to top Bottom Total Depth of Well 4465 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	380.27'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/mud to 620'
Set plug, 25 sx cement.
Filled hole to 360', set
plug 20 sx cement. Filled
hole to 40'. Set plug 1/2
sx hulls 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1964

04-27-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling
Address Box 173--Russell, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Maxine V. Head (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Head

1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of April, 19 64

Jean Hollas

Notary Public.



DRILLERS LOG

No. 1 F.J. Rhoades

CASING RECORD: 8 5/8" @ 380.27 w/200 sx cement
 COMPANY: Tidewater Oil Company
 CONTRACTOR: Red Tiger Drilling Co.
 COMMENCED: April 9, 1964
 TOTAL DEPTH: 4465' COMPLETED: April 22, 1964
 DESCRIPTION: C SE NW 14-14S-27W Gove Co., Kansas
 ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod	0	115	
Blue Shale	115	380	
Shale & Shells	380	1290	
Redbed & Shale	1290	1314	
Blain Anhydrite	1314	1321	
Shale	1321	1397	
Anhydrite	1397	1424	
Shale & Shells	1424	1776	
Redbed Shale & Shells	1776	1954	
Shale & Lime	1954	1993	
Shale Shells & Redbed	1993	2185	
Shale & Lime	2185	3530	
Lime	3530	4025	
Shale & Lime	4025	4258	
Lime	4258	4395	
Shale & Lime	4395	4442	
Lime & Chert	4442	4465	

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1964

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Head
Maxine V. Head

Subscribed and sworn to before me this 24th day of April, 1964.

Jean Hollan
Notary Public

My Commission Expires:
5-22-66

