


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-063-20080-00-00
WELL PLUGGING RECORD

Gove County, Sec. 11 Twp. 14 Rge. 27W(E) (W)

Location as "NE/CNW%SW%" or footage from lines SE NE
Lease Owner Chief Drilling Co., Inc.
Lease Name Jones Well No. 1
Office Address Suite 905 Century Plaza, Wichita, Kans., 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed August 17, 1971 19
Application for plugging filed August 16, 1971 19
Application for plugging approved August 16, 1971 19
Plugging commenced August 17, 1971 19
Plugging completed August 17, 1971 19
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3750 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	256'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 975' w/100 sacks cement
Plugged through drill pipe @ 275' w/20 sacks cement
Plugged through drill pipe @ 40' w/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1971
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
Suite 905 Century Plaza, Wichita, Kans.
(Address)

Subscribed and Sworn to before me this 17th day of August, 1971



February 16, 1974

Karen E. Duarte
Karen E. Duarte Notary Public.

15-063-20080-00-00
 RECEIVED
 STATE CORPORATION COMMISSION
 AUG 24 1971
 CONSERVATION DIVISION
 Wichita, Kansas

WELL LOG

CHIEF DRILLING CO., INC.
 Suite 905 Century Plaza
 Wichita, Kansas 67202

R JONES
 SE NE Sec. 11-14-27W
 Gove County, Kansas

CONTRACTOR: Company Tools
 CASING RECORD: Set 265' of 8 5/8"
 w/180 sacks common quick set

Commenced: 8/11/71
 Completed: 8/17/71

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand & Clay	0	100	2547 Gr.
Sand, Clay & Shale	100	310	2549 D.F.
Shale & Sand	310	1997	2552 K.B.
Anhydrite	1997	2035	
Shale & Shell	2035	2695	
Lime & Shale	2695	3750	
Total Depth	3750		
			<u>FORMATION TOPS</u>
			Anhydrite 1997 + 555
			Base Anhy. 2035 + 517
			Heebner 3744 - 1192
			T.D. 3750 - 1203

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE NE Sec. 11-14-27W, Gove County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
 Jim Robinson, Office Manager

Subscribed and sworn to before me this 23rd day of August, 1971.

Karen E. Duarte
 Karen E. Duarte, Notary Public

