

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

#2

API NUMBER 15-169-20,305-00-00

LEASE NAME Mai

WELL NUMBER 1

10 Ft. from S Section Line

1550 Ft. from E Section Line

SEC. 34 TWP. 14 RGE. 2 (N) or (W)

COUNTY Saline

Date Well Completed 6/18/90

Plugging Commenced 6/18/90

Plugging Completed 6/18/90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Tenex Oil Corporation

ADDRESS P.O. Box 3047, Olathe, Ks. 66062-3047

PHONE#(913) 791-2621 OPERATORS LICENSE NO. 8921

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 15, 1990 (date)

by Johnny Sanders (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Simpson Depth to Top \_\_\_\_\_ Bottom 3669 T.D. 3669

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Simpson	Dry	210	0	8-5/8"	210	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Drill to rotary total depth of 3669'. Fill hole with heavy mud to 700'. Set plug with 50 sacks cement. Fill hole with heavy mud to 300'. Set plug with 50 sacks cement. Fill hole with heavy mud to 60'. Set plug with 35 sacks cement. Plug rathole with 10 sacks cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Tornado Drilling, Inc. License No. 3890

Address P.O. Box 37, Canton, Kansas 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Tenex Oil Corporation


STATE OF Kansas COUNTY OF McPherson, ss.

Terry P. Bandy (Agent)

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry P. Bandy

(Address) P.O. Box 37, Canton, Ks. 67428



1990  
06-25-1990  
CONSERVATION DIV.  
Wichita, Kansas

Subscribed and sworn to before me this 22nd day of June, 1990

Cynthia G. Reimer  
Notary Public

My Commission Expires: May 15, 1994

15-1109-20305-00-00

TORNADO DRILLING, INC.  
P.O. BOX 37  
CANTON, KANSAS 67428

June 22, 1990

COMPANY: TENEX OIL CORPORATION  
 CONTRACTOR: TORNADO DRILLING INC.  
 FARM: MAI #1  
 LOCATION: 10' FSL & 1550' FEL SECTION 34-14S-2W  
 SALINE COUNTY, KANSAS  
 COMMENCED: JUNE 11, 1990  
 COMPLETED: JUNE 18, 1990  
 ELEVATION: 1430 GL. 1435 K.B.

0	to	45	Soil & Clay
45	to	160	Shale & Lime
160	to	220	Lime
220	to	1515	Shale & Lime
1515	to	1815	Shale
1815	to	2115	Lime & Shale
2115	to	2656	Lime with Shale Streaks
2656	to	3070	Lime
3070	to	3415	Lime & Shale
3415	to	3669	Lime, Simpson
		3669	Rotary Total Depth


Drill 12½" hole to 220'. Set 8-5/8" 20# surface casing at 210'. Cement with 135 sacks 60/40 Pozmix 2% gel, 3% Calcium Chloride. Plug down at 1:00 A.M., June 12, 1990. Drill 7-7/8" hole to Rotary Total Depth of 3669'. Fill hole with heavy mud to 700'. Set plug with 50 sacks of cement. Fill hole with heavy mud to 300'. Set plug with 50 sacks of cement. Fill hole with heavy mud to 60'. Set plug with 35 sacks cement. Plug rathole with 10 sacks cement. Plugging finished at 12:00 P.M., June 18, 1990.

CERTIFICATE

I, Terry P. Bandy, President of Tornado Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Mai #1 located on the 10' FSL and 1550' FEL Section 34-14S-2W, Saline County, Kansas as is reflected by the files of Tornado Drilling, Inc.

*Terry P. Bandy*  
 Terry P. Bandy, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 22nd day of June, 1990.



*Cynthia G. Reimer*  
 Cynthia G. Reimer-Notary Public