

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Saline County, Sec. 22 Twp. 14S Rge. (E) 2 (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner Earl F. Wakefield & etal

Lease Name Thelander Well No. 1

Office Address 307 Union Nat'l Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 29 19 56

Application for plugging filed June 29 19 56

Application for plugging approved June 29 19 56

Plugging commenced June 29 19 56

Plugging completed June 29 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, McPherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3399 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	235'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with mud to 210'  
15 sacks cement  
Mud to 18'  
Cement to surface

Name of Plugging Contractor Earl F. Wakefield  
Address 307 Union National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Earl F. Wakefield (employee or owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield  
307 Union Nat'l Bank Bldg.  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of July, 19 56

My commission expires July 26, 1958

C. A. Snow Notary Public.

PLUGGING  
FILE SEC 22 T 14 R 2W  
BOOK PAGE 77 LINE 5

JUL 5 1956  
07-09-1956  
CONSERVATION DIVISION  
Wichita, Kansas

15-169-00082-00-00

LEASE: Thelander #1  
OWNER: Earl F. Wakefield & Etal  
CONTRACTOR: Earl F. Wakefield  
COMM: 6/15/56 COMP: 6/29/56

LOCATION: SW SW NW 22-24S-2W  
Saline County, Kansas  
CASING: 8 5/8" Set @ 235

Elevation: 1279 K.B.

Surface	235
Lime & Shale	275
Shale & Shells, Lime Stks.	370
Lime & Shale	430
Shale & Shells	777
Shale & Lime	1730
Shale	1780
Lime & Shale Stks.	1840
Shale	1975
Shale & Lime	2598
top K.C. @1975	
Lime	2602
Shale & Lime	2627
Lime ( Mississippi)	2855
Shale & Lime	2898
Shale	2965
Lime (Hunton)	3103
Shale & Lime	3136
top Sylan Shale @3103	
Shale	3163
Shale & Lime	3210
Lime	3325
Shale	3334
Lime & Sand	3391
Lime	3399
Total Rotary Depth	3399

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I hereby certify that the above is a true and correct copy of the log of the Thelander #1 well located SW SW NW 22-24S-2W, Saline County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 6<sup>th</sup> day of July, 1956

[Signature]



My Commission Expires: 7-26-58

PLUGGING  
FILE SEC 22 T 14 R 2W  
BOOK PAGE 77 LINE 5

RECEIVED  
JUL 9 1956  
07-09-1956  
DIVISION  
Salina, Kansas