

15-169-00773-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Saline County. Sec. 18 Twp. 14 Rge. 2 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE/4
Lease Owner Charles E. Petrey
Lease Name Duncan-JILKA Well No. 1
Office Address McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 11-7-62 19
Plugging completed 11-11-62 19
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3193 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	173'	None
				5-1/2"	3191'	2638'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3190', sanded to 3176' and dumped 5 sacks of cement @ 3176' with dump bailer. Pulled 1 jt. of 5 1/2" casing, well started flowing, pumped in 20 sacks of gel mud and 20 sacks of weight mud. Pulled balance of 5 1/2" casing and squeezed well with 100 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

JAN 2 1963
01-02-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1962

Milton J. Volin
Notary Public.

My commission expires May 20, 1964



15-169-00773-00-00

LOG

DUNCAN-JILKA #1

NE/ Section 18-149-2W

A.C. BOLLER and E.A. KEYS

NOV 11-05 1947

Commenced: January 12, 1947
Completed: January 25, 1947

Lime & Shells	0	210
Anhydrite & Shale	210	280
Shale, Lime & Sand Stks	280	430
Lime, Shale & Sand	430	570
Lime & Stks. Shale	570	630
Shale & Lime Shells	630	815
Lime & Shale Stks	815	918
Lime & Shale	918	1099
Shale & Shells	1099	1390
Lime & Shale Stks.	1390	1530
Shale	1530	1585
Shale & Stks Lime	1585	1710
Shale & Lime	1710	1870
Shale & Lime Stks.	1870	1950
Shale & Lime	1950	2010
Lime & Shale Stks	2010	2683
Cherty Lime	2683	2691
Lime	2691	2747
Lime & Shale, Cherty	2747	2856
Lime & Shale	2856	2881
Shale	2881	2999
Cherty Lime	2999	3004
Lime & Shale, Cherty	3004	3051
Lime	3051	3114
Shale	3114	3191
Lime, Top Viola	3191	3193
Total Depth		3193

CASING RECORD

8-5/8" casing set at 173' and cemented with 80 sacks cement, & 200# calcium chloride.

5-1/2" casing set at 3191' and cemented with 75 sacks cement.