


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-169-00772-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

McPherson County. Sec. 18 Twp. 14 Rge. 2 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE/4 SW/4 NE/4
Lease Owner Chas. E. Petrey
Lease Name White-Duncan Well No. 1
Office Address 1300 No. Maple
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed August 30 1946
Application for plugging filed December 26 1953
Application for plugging approved About January 1954
Plugging commenced January 8 1954
Plugging completed January 14 1954
Reason for abandonment of well or producing formation Non-profitable

If a producing well is abandoned, date of last production December 1 1953
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Viola lime Depth to top 3220 Bottom 3222 Total Depth of Well 3222 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Viola Lime				5 $\frac{1}{2}$ "	3218	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3222 to 3210 ft. Sand bridge.
3210 to 3180 ft. 5 sks. cement.
3180 to 196 ft. Mudded.
196 to 185 ft. Rock bridge.
185 to 140 ft. 15 sks. cement.
140 to 15 ft. Mud.
15 ft. to cellar 5 sks. cement.

CONC-01-29-1954
WICHITA DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Chas. E. Petrey
Address 1300 No. Maple McPherson, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.
Chas. E. Petrey (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Chas E Petrey
1300 No. Maple McPherson, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28th day of January, 1954.
My commission expires July 15, 1955.

David Pauli
Notary Public.

28-3273-s 4-50-10M



PLUGGING
FILE SEC 18 T 14 R 2W
BOOK PAGE 2 LINE 1

15-169-00772-00-00

WHITE DUNCAN #1

NE/4 SW/4 NE/4 of Sec.18-14-2W
Saline County, Kansas
Elevation 1261' D.F.

Well drilled August 1946.

Casing Record
196' of 8 5/8"
3218' of 5 1/2" Cemented with 75 sacks

Shale & Shells	0	196
Lime & Shale	196	260
Lime Shale & Sand	260	365
Lime & Shale	365	510
Shale & Sand	510	616
Lime & Shale	616	2222
Lime Soft	2222	2244
Lime & Shale	2244	2718
Cherty Lime & Shale	2718	2862
Shale	2862	2890
Cherty Lime & Shale	2890	2912
Lime & Shale	2912	3034
Soft sandy Lime	3034	3048
Lime & Shale Cherty	3048	3106
Lime & Shale	3106	3203
Shale	3203	3220
Chert & Dolomite	3220	3222
Top of Viola	3220	
Total Depth	3222	

PLUGGING
FILE SEC 18 T 14 R 2W
BOOK PAGE 2 LINE 1

12-17-1953