

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-051-24,313-00-00

LEASE NAME Lang

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

1540 Ft. from S Section Line

2720 Ft. from E Section Line

LEASE OPERATOR Ernst & Steidle Oil Operators

SEC. 12 TWP. 14 RGE. 17 (X) or (W)

ADDRESS Box 859 Russell, KS 67665

COUNTY Ellis

PHONE# (913) 666-4468 OPERATORS LICENSE NO. 6261

Date Well Completed 9-11-85

Character of Well D&A

Plugging Commenced 9-11-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-11-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Ed Schumaker
 to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3505

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 3500' w/20 sacks 60/40 pozmix 6% gel thru drill pipe
 Next Plug: @ 1110' w/20 " " " " "
 Next Plug: @ 510' w/100 " " " & 1 sack Seal Flake
 Top Plug: @ 40' Bridged Plug - 10 sacks cement (10 sacks in Rat Hole)
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Co. License No. 5864

Address Box 877 Great Bend, KS 67530


STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 17th day of Sept., 19 85



Deborah M. Hague
 Notary Public

STATE COMMISSION Expires: 4-29-86

SEP 20 1985
 09-20-1985
 CONSERVATION DIVISION
 Wichita, Kansas

15-051-24313-00-00

DRILLER'S WELL LOG

DATE COMMENCED: September 7, 1985
DATE COMPLETED: September 11, 1985

Ernst & Steidle Oil Operators
LANG #1
Approx. SE NE SW
Sec. 12, T14S, R17W
Ellis County, Ks.

ELEVATION: 1940 K.F.

0 - 1100' Surface Soil, Sand, Shale
1100 - 1151' Anhydrite
1151 - 2955' Lime & Shale
2955 - 3177' Lime
3177 - 3181' Shale
3181 - 3197' Lime & Shale
3197 - 3474' Lime
3474 - 3505' Dolomite
3505' RTD

FORMATION DATA

Anhydrite 1100'
Topeka 2955'
Haebner 3177'
Toronto 3181'
Lansing 3221'
Arbuckle 3474'
RTD 3505'

Surface Pipe: Set new
8-5/8", 22# pipe @259'
w/150 sacks 60/40 pozmix
2# gel 3# cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

and sworn to before me this 18 day of September 1985.

Signature:

Dorothy M. Wague
Notary Public



RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1985
09-20-1985
CONSERVATION DIVISION
Wichita, Kansas