


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 9 Twp. 14S Rge. 17W (SE/4 SW/4)  
Location as "NE/CNW/SW" or footage from lines NW/4 SE/4 SE/4  
Lease Owner Birmingham-Bartlett Drilling Co.  
Lease Name Goetz "A" Well No. 1  
Office Address 300 Kaufman Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed November 6 1956  
Application for plugging filed August 21 1957  
Application for plugging approved August 21 1957  
Plugging commenced August 22 1957  
Plugging completed August 27 1957  
Reason for abandonment of well or producing formation No longer a commercial  
producer

If a producing well is abandoned, date of last production July 30 1957  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation Arbuckle Depth to top 3528 Bottom 3551' Total Depth of Well 3551 Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	181'	8-5/8"	182'	None
		0	3530'	5-1/2"	3530'	2882'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3533' and found it open.  
filled w/sand to 3515' and ran 4 sacks of  
cement to 3485'. Pulled 72 jts. 5 1/2' casing,  
pumped 35 sacks of gel mud, pulled 5 jts.  
and pumped 20 sacks of cement. Pulled to 220'  
and pumped 15 sacks of cement. Mudded the  
hole to 35' and filled w/cement to top.



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDWICK, ss.  
Chas. H. Keever, Prod. Supt. of Birmingham-Bartlett Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Chas. H. Keever  
Willow Road, R-3 Hutchinson  
(Address)

Subscribed and sworn to before me this 29th day of August, 1957.  
Thomas V. Duggin  
Notary Public.



PLUGGING  
FILE SEC. 9 T. 14 R. 17W  
BOOK PAGE 39 LINE 8

15-051-00418-00-00

GOETS "A" NO. 1 WELL

LOCATION: NW/4 SE/4 SE/4  
Section 9-14S-17W  
Ellis County, Kansas  
SPUDDED: 10-24-56  
COMPLETED: 11-3-56

OWNER, OPERATOR  
and CONTRACTOR: Birmingham-Bartlett Drilling Co.  
300 Kaufman Building  
Wichita 2, Kansas

SURFACE CASING: 8-5/8" casing cemented at 181' with  
165 sacks cement and 2 c.c.

OIL STRING: 5-1/2" 14# casing cemented at 3530'  
with 125 sacks cement

LOG

(Figures indicate bottom of formation)

0 - 675	Shale and shells
825	Sand and shale
1180	Shale and red bed
1224	Anhydrite
1360	Shale and shells
1875	Shale
2628	Shale and lime
2835	Shale and shells
3300	Lime and shale
3532	Lime
3532	Rotary Total Depth

The undersigned, Richard Lindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Goets "A" No. 1 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Lindery

Subscribed and sworn to before me  
this 5th day of November, 1956.

Beverly Larson

Beverly Larson, Notary Public

My Commission expires October 2, 1958.



PLUGGING  
FILE SEC 9 T 14 R 17 W  
BOOK PAGE 39 LINE 8