

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,285-00-00

LEASE NAME Sanders

WELL NUMBER 3

4020 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 9 TWP. 14S RGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed 8-14-85

Plugging Commenced 8-14-85

Plugging Completed 8-14-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS P.O. Box 8647, Wichita, Kansas 67208

PHONE# (316) 682-3022 OPERATORS LICENSE NO. 8061

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3616'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surf.	208	8-5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
25 sx. @ 1250', 100 sx. @ 880', 40 sx. @ 220', 10 sx. @ 40', 10 sx. in
Rathole.

60/40 Pozmix, 3% CC, 4% Gel & 1 sx. Cello Flake

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Woodman-Iannitti Drlg. Co. License No. 5122

Address P.O. Box 308, Great Bend, Kansas 67530

STATE OF _____ COUNTY OF _____, ss.


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John S. Weir

(Address) John S. Weir, President
P.O. Box 8647 Wichita, Kansas 67208

SUBSCRIBED AND SWORN TO before me this 20th day of September, 19 85

A. M. Miller Notary Public



Commissioner of State Corporation Commission

RECEIVED
SEP 23 1985
09-23-1985
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84

K. T. WOODMAN
RES. PHONE (316) 733-0418
OFF. PHONE (316) 265-7650
WICHITA, KANSAS

15-051-24285-00-00

D. J. IANNITTI
PHONE (316) 792-2921
GREAT BEND, KANSAS

WOODMAN-IANNITTI DRILLING COMPANY

Rotary Drilling Contractors
704 UNION CENTER BUILDING
WICHITA, KANSAS 67202

Company:	Oil Producers, Inc. of Kansas
Farm:	Sanders #3
Location:	60'N of C W/2 W/2 NW
Section:	9-14S-17W
County:	Ellis
Contractor:	Woodman-Iannitti Drilling Company
Comm:	August 10, 1985
Comp:	August 14, 1985
Casing:	8-5/8" 20# set @ 208' w/140 sx. 3% CC, 2% Gel.

Figures Indicate Bottom Formations:

208	Shale & Lime
342	Shale
680	Shale, Sand & Shells
880	Dakota Sand
1135	Shale
1216	Shale & Lime
1253	Anhydrite
1687	Lime & Shale
2150	Shale & Lime
2400	Shale & Lime
2725	Lime & Shale
3005	Lime & Shale
3205	Lime & Shale
3340	Shale & Lime
3460	Lime & Shale
3585	Lime
3616	Arbuckle

I certify the above to be a true and correct copy of the Drillers Log to the best of my knowledge and belief.

WOODMAN-IANNITTI DRILLING COMPANY

Peter L. Iannitti
Peter L. Iannitti

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1985
09-23-1985
CONSERVATION DIVISION
Wichita, Kansas