


15071200180000

Form GP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Greeley County, Sec. 29 Twp. 18S Rge. 40W (E9X) (W)
Location as "NE/CNW/SW" or footage from lines C SW
Lease Owner Dorchester Exploration, Inc.
Lease Name Brinkman Well No. 1
Office Address 1201 Vaughn Building, Midland, Texas 79701
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 26, 1974 19
Application for plugging filed February 26, 1974 19
Application for plugging approved February 26, 1974 19
Plugging commenced 4:00 PM, February 26, 1974 19
Plugging completed 5:30 PM, February 26, 1974 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3000' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	240'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Spotted 110 cu. ft. through drill pipe at 1250'.
Spotted 30 cu. ft. through drill pipe at 250'.
Pumped 10 cu. ft. from 40' to base of cellar.
2 sacks in rathole.

RECEIVED
STATE CORPORATION COMMISSION
3-15-74
MAR 15 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor STERLING DRILLING COMPANY
Address P. O. Box 129, Sterling, Kansas 67579



STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY
(Signature) F. A. Wuellner
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 74.

Bernard Laudermilk
Bernard Laudermilk, Notary Public.

15-071-20018-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - BRINKMAN #1
Located: C SW, Section 29-18S-40W, Greeley County, Kansas

OWNER: Dorchester Exploration, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 22, 1974
COMPLETED: February 26, 1974

TOTAL DEPTH: 3000'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 1982 Sand and Shale	Ran 5 joints 8 5/8" 8rd 20# Range 3 new casing, 228.87' set at 240' K.B. with 200 sacks 60/40 Pozmix, 3% cc, 1/4# flocele per sack. Plug down at 10:15 PM, 2-22-74.
1982 - 2190 Salt	
2190 - 2245 Salt and Shale	
2245 - 2539 Shale and Shells	
2539 - 2565 Anhydrite	
2565 - 2700 Shale and Sand Lime	
2700 - 2870 Shale and Shells	
2870 - 3000 Lime and Shale	

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1974
CONSERVATION DIVISION
Wichita, Kansas