

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 33971 Name: TriPower Resources, LLC Address 1: P.O. Box 849 Address 2: City: Ardmore State: OK Zip: 73402 + 0849 Contact Person: Neal Hill Phone: (580) 226-6700 Type of Well: (Check one) [X] Oil Well [] Gas Well [] OG [] D&A [] Cathodic [] Water Supply Well [] Other: [] SWD Permit #: [] ENHR Permit #: [] Gas Storage Permit #: Is ACO-1 filed? [] Yes [] No If not, is well log attached? [] Yes [] No Producing Formation(s): List All (If needed attach another sheet) Mississippi - Depth to Top: 2631 - Bottom: 2642 - T.D. 2800

API No. 15 - 015-22346 · 00.00 Spot Description: S/2, NE, SE Sec. 26 Twp. 24 S. R. 4 [X] East [] West 1,650 Feet from [] North / [X] South Line of Section 660 Feet from [X] East / [] West Line of Section Footages Calculated from Nearest Outside Section Corner: [] NE [] NW [X] SE [] SW County: Butler Lease Name: Mingenback Well #: 1 Date Well Completed: 10/14/1983 The plugging proposal was approved on: 7/7/11 (Date) by: Shane Jones (KCC District Agent's Name) Plugging Commenced: 7/7/11 Plugging Completed: 7/7/11

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include Surface and Production casing data.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 50 sx 60/40 Poz +4% gel + 3% CaCl + 1/2 #/sx floccell through tubing at PBTD. Pulled tubing. Set cast iron bridge plug @ 300' KB. Shot perfs in 4.5" casing at 260' KB. Cemented from 260' to surface with 107 sx 60/40 Poz + 4% gel. Good circulation in annulus. Cement standing inside 4.5" casing. WOC 24 hours. Cut off surface and production casing 4.5' below ground level. Filled cellar and leveled surface.

Plugging Contractor License #: 5870 Name: Phillips Well Service Address 1: P.O. Box 1263 Address 2: City: El Dorado State: KS Zip: 67042 + 1263 Phone: (316) 321-6650 Name of Party Responsible for Plugging Fees: TriPower Resources, LLC State of Oklahoma County, Carter, ss. Dub Curry (Print Name) [X] Employee of Operator or [] Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: M. B. Curry

RECEIVED JUL 18 2011