

STATE OF KANSAS
STATE CORPORATION OF COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-071-20,565-0000

LEASE NAME Williams

WELL NUMBER 1-22

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2200 Ft. from N Section Line

330 Ft. from W Section Line

SEC. 22 TWP. 18S RGE. 42W (E) or (W)

COUNTY Greeley

LEASE OPERATOR Leede Oil & Gas, Inc.

ADDRESS 6400 S Fiddler's Green Cr., Ste 2100, Englewood, CO

PHONE# (303) 629-1523 OPERATORS LICENSE NO. 30994

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 07/10/92

Plugging commenced 07/11/92

Plugging completed 07/11/92

The plugging proposal was approved on 07/11/92 (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Tight	surface		8-5/8"	320'	
Atoka	"					
Mississippian	"					
St. Louis	"					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

50 sacks 2560', 50 sacks 1500', 50 sacks 800', 40 sacks 340', 10 sacks 40', 15 sacks rat hole, 10 sacks mouse hole. 60/40 poz, 6% Gel. JC: 7:30pm 07/11/92 -- Allied

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Leede Oil & Gas

STATE OF Colorado COUNTY OF Arapahoe, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 13886, Denver, CO 80201

SUBSCRIBED AND SWORN TO before me this 10th day of August, 1992

[Signature]

Notary Public [Signature]
RECEIVED
CONSERVATION COMMISSION



My Commission Expires: _____

My commission expires: 08-27-04
8500 E. Arapahoe Rd.
Englewood, CO 80112

8-12-92
AUG 12 1992

EFFECTIVE DATE: 6-22-92

State of Kansas NOTICE OF INTENTION TO DRILL 071-20,565-0000

FORM MUST BE TYPED FORM MUST BE SIGNED ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date June 25 1992 month day year

Spot SW SW NW Sec 22 Twp 18 S, Rg 42 East West

OPERATOR: License # 30994 Name: Leede Oil and Gas, Inc. Address: 6400 S. Fiddlers Green Circle, #2100 City/State/Zip: Englewood, CO 80111 Contact Person: D. E. Wood/DRW Operating Company Phone: (303) 629-1523

2200' feet from South / North line of Section 330' feet from East / West line of Section IS SECTION X REGULAR IRREGULAR

CONTRACTOR: License #: 30606 Name: Murfin

(NOTE: Locate well on the Section Plat on Reverse Side) County: Greeley Lease Name: Williams Well #: 1-22 Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment: X Oil ... Enh Rec ... Infield X Mud Rotary ... Gas ... Storage ... Pool Ext. ... Air Rotary ... OUVO ... Disposal X Wildcat ... Cable ... Seismic; ... # of Holes ... Other

Is this a Prorated/Spaced Field? ... yes X no 1 Target Formation(s): Mississippian Nearest lease or unit boundary: 330' Ground Surface Elevation: 3796' feet MSL Water well within one-quarter mile: ... yes X no Public water supply well within one mile: ... yes X no Depth to bottom of fresh water: 110 Depth to bottom of usable water: 120 Surface Pipe by Alternate: ... 1 X 2 Length of Surface Pipe Planned to be set: 200' Length of Conductor pipe required: N/A Projected Total Depth: 5550' Formation at Total Depth: Mississippian Water Source for Drilling Operations: ... well X farm pond ... other

If OUVO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth:

Directional, Deviated or Horizontal wellbore? ... yes X no If yes, true vertical depth: Bottom Hole Location:

DWR Permit #: N/A Will Cores Be Taken? ... yes X no If yes, proposed zone: 200' Alt. II Req.

Exp. 12/22/92

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that the following minimum requirements will be met:

Pusher Bourne Meyer 563 SPUD DATE 7-2-92 INIT. SM LENGTH SURFACE PLANNED 300' RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 5/8" @ 3 2 1/2 CONDUCTOR ANHYDRITE T- 25 1/4 B- ELEVATION TD 5300 FORMATION M, J, S RAN PIPE @ DV TOOL ALT II DONE SX Y N Ar buckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 2560 Ft. W/ 50 SX 1/2 Base Anyh. @ 1500 Ft. W/ 50 SX 1/2, 1/2 Plug @ 800 Ft. W/ 50 SX Bottom Surface @ 340 Ft. W/ 40 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN D.O. DATE 7-11-92 TYPE OF CEMENT 60/40 690 STARTING TIME (AM/PM) DATE 7-11 COMPLETION TIME 7:30 (AM/PM) DATE 7-11 CEMENT COMPANY 1992 DIVISION COMMISSION