

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-12302-00-00

LEASE NAME Frey #A-5 SWD

WELL NUMBER \_\_\_\_\_

SPOT LOCATION SW NE NE

SEC. 7 TWP. 21 RGE. 14w (E) or (W)

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 2/13/85

Plugging Completed 2/15/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR N.C.R.A.

ADDRESS Box 1404, McPherson, Ks. 67460

PHONE # (316) 241-2340 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4214'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	880'	none
				5 1/2"	3902'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plug Job - No pipe recovery. Pumped well with 3 hulls, 400 sacks 60/40 poz 2% gel 3% c.c. & 3 hulls. Checked hole down 5 1/2" & down 8 5/8. Found top of cement plug at 650'. Ran 6 1/2 yard Ready-Mix from 650' to base of cellar.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED RECEIVED  
STATE CORPORATION COMMISSION  
FEB 19 1985  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 18th day of February, 1985

IRENE HOOVER  
State of Kansas  
My Comm. Exp. Aug. 15, 1985

Irene Hoover  
Notary Public

My Commission expires: \_\_\_\_\_

15-185-12302-00-00

**COPY**

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 East Murdock


Wichita, Kansas

Company - THE VICKERS PETRO. CO., INC.  
Farm - Frey "A" No. 5

SEC. 7 T. 21 R. 14W  
SW NE NE

Total Depth. 4214  
Comm. 7-22-51 Comp. 8-6-51  
Shot or Treated.  
Contractor.  
Issued. 9-8-51

County. Stafford  
KANSAS



Elevation. 1929 RB

Production. STD

Figures Indicate Bottom of Formations.

CASING:  
8 5/8" 880' cem. w/400 sx  
5 1/2" 3902' cem. w/75 sx

sand & shale	210
shale blue & shells	280
shale & shells	308
sand	410
red beds, shale & sand	810
red beds	878
anhydrite	901
red beds, shale & shells	1260
shale & shells	1375
shale, shells & salt	1615
lime & shale	1885
lime broken & sand	2000
lime & sand	2080
lime & shale	2905
lime	2990
lime & shale	3090
lime	3190
lime & shale	3297
shale	3370
lime & shale	3644
conglomerate	3847
dolomite	4214
Total Depth	

Tops:	
Heebner	3268
Brown Lime	3370
Lansing	3380
Conglomerate	3644
Arbuckle	3847

**K. G. S. LIBRARY**

RECEIVED  
STATE CORPORATIONS COMMISSION

JAN 15 1965

CONSERVATION DIVISION  
Wichita, Kansas