

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32278
Name: Tengasco, Inc.
Address 1: 1327 Noose Rd
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Gary Wagner
Phone: (785) 625-6374
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 009-24,422 -00-00
Spot Description: _____
_____NW NW SW Sec. 19 Twp. 20 S. R. 15 East West
2,310 Feet from North / South Line of Section
4,950 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barton
Lease Name: Iannitti Well #: 4
Date Well Completed: _____
The plugging proposal was approved on: 05/11/2010 (Date)
by: Bruce Rodie (KCC District Agent's Name)
Plugging Commenced: 06/11/2010
Plugging Completed: 06/16/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	1135'	0'
		Production	5-1/2"	3879'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

06/11/10 - Drove to location. Rig up. Pull 118 jts of 2-7/8" tubing. Break well head off. Rig up casing jacks - could not get any stretch on casing. Rig jacks down. Rig over to run tubing. Unload tubing. Clean tools. Shut down for day.
06/16/10 - Drove to location. Perf @ 1656', 1150', 500'. Tally tubing in hole. Spot 1st plug @ 3700' w/50 sacks, 17 gel - 200# hulls. Pull 65 jts. 2nd plug - 1656' w/90 sacks - 300# hulls. Pull 28 jts. Circulate to surface @ 800'. Did not come around. Finish pulling tubing. Allied pumped cement down casing @ 500 PSI. Rig down.

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc.
Address 1: 1822 24th Street Address 2: _____
City: Great Bend State: Kansas Zip: 67530 + _____
Phone: (620) 793-5838
Name of Party Responsible for Plugging Fees: Tengasco, Inc.
State of Kansas County, Barton, ss.
Tim Dickson Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tim Dickson

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 30 2010
6-30-10
CONSERVATION DIVISION
WICHITA, KS