

4-041447

15.05120238.00.00

87
R

TO
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 5-16-68

SE SW SE /4 SEC. 27 , 13 S, 20 W
330 feet from S section line
1650 feet from E section line

Operator license# 3613 Lease Giebler well # 1

Operator: Hallwood Petroleum, Inc. County Ellis

Address: 4582 So. Ulster St. Pkwy. Well total depth 3856 feet ^{125.32}
Suite 1700 Conductor Pipe: 0 inch @ 0 feet
Denver, Colorado 80237 Surface pipe 8 5/8 Inch @ 213 feet
w/150 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 10:00A.M Day: 22 Month: March Year: 93

Plugging proposal received from: Aven Weaverling

Company: Hallwood Petroleum, Inc. Phone:

Were: 4 1/2" casing set @ 3854' w/125 sx. cement. Perf. @ 3806'-3816'.
Perf. @ 1580'. Dakota @ 780'.

Ordered 250 sx. 60/40 pozmix - 10% gel. with 1/4# flocele plus 400# hulls
plus 12 sx. gel.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 3:00P.M., Day: 23, Month: March, Year: 93

Actual plugging report: M.I.R.U. - R.I.H. with tubing to 3791'.
Spot 20 sx. cement with 100# hulls on bottom, followed with 8 sx. gel.
spacer to 1610'. Pull tubing to 1610' - spot 75 sx. cement w/200#
hulls to circulate at surface. P.O.O.H. with tubing. Squeeze 65
additional sx. cement. Max. 500#. S.I. 300#. Hooked-up to 8 5/8" S.P.
Pumped in 50 sx. cement with 100# hulls. Max. 700# P.S.I. S.I. 200#.

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING . Elevation: GL

I did not observe the plugging.

Dennis L. Hamel
CONSERVATION DIVISION
Wichita, Kansas

(agent)

Form CP-2/3

4-8-93
37555

3-23

RECEIVED
STATE CORPORATION COMMISSION

APR 6 1993