

API NUMBER 19-051-21, 258

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

$E\frac{1}{2}$  SE SW, SEC. 27, T 13 S, R 20 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 4655  
Operator: B.H.P. Petroleum (America) Inc.  
Name & Address: 925 Patton Road  
Coast Bend, Kans.  
67530

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line  
Lease Name Geibler Well "A" #2  
County Ellis, Co. 124.80  
Well Total Depth 3840 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hulliburton Drilling Co License Number \_\_\_\_\_

Address East Hwy 40 Haep, Kans. 67601

Company to plug at: Hour: 11:15 AM Day: 6<sup>th</sup> Month: Aug. Year: 1986

Plugging proposal received from Geo. Sutton

(company name) B.H.P. Petroleum (America) Inc (phone) 316-792-2756

were: 8 5/8" - 308<sup>ft</sup> SP. CUC #1175<sup>SK</sup> cmt, 5 1/2" csg set @ 3839 #1175<sup>SK</sup> cmt.

P.B.T.D 3828; Peryo 3833 #1 to 3245; Port Collar @ 1507<sup>ft</sup>

CUC #1/300<sup>SK</sup> cmt, Proposal Order 300<sup>SK</sup> Econolite

65/35 Permiox Gel - 2% additive and 6<sup>SK</sup> shells with pump truck.

Pump in Annulus with cement and pressure spot and circulate

Cement. Plugging Proposal Received by Marston Schmidt (TECHNICIAN)

Plugging Operations attended by Agent? All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 AM Day: 6<sup>th</sup> Month: Aug. Year: 1986

ACTUAL PLUGGING REPORT Ordered 300<sup>SK</sup> 65/35 Permiox 10% Gel, 2%

Abbluise (Econolite) and 6<sup>SK</sup> shells.

Used on to Annulus pressured to 700 P.S.I. No bit pumped in.

With 2 7/8" tubing spotted #150<sup>SK</sup> cmt #1/4<sup>SK</sup> shells mixed in

@ 3827, and spotted @ 2565<sup>ft</sup> #1/100<sup>SK</sup> cmt #1/2 shells

Cement Circulated. Squeezed 5 1/2" csg #1/40<sup>SK</sup> cmt #1/2<sup>SK</sup> shells mixed.

Remarks: In. max pressure 750 P.S.I. Cemented by Hulliburton

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Marston Schmidt (TECHNICIAN) 8-8-86

ANG 12 1986

08-11-86

SEP 10 1986