

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21157-00-00  
Spot: E2NENWNW Sec/Twnshp/Rge: 27-13S-20W  
330 feet from N Section Line, 1120 feet from W Section Line  
Lease/Unit Name: BEFORT-WALDSCHMIDT Well Number: 1  
County: ELLIS Total Vertical Depth: 3890 feet

Operator License No.: 6892  
Op Name: TRICH PRODUCTION, INC.  
Address: PO BOX 1408 300 N. GREEN STREET ST  
LONGVIEW, TX 75606

Conductor Pipe: Size feet: 9/26.43  
Surface Casing: Size 8.625 feet: 220 w/175 sxs cmt  
Production: Size 5.5 feet: 3889 w/175 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/06/2002 8:30 AM  
Plug Co. License No.: 6892 Plug Co. Name: TRICH PRODUCTION, INC.  
Proposal Rcvd. from: MIKE STANTON Company: TRICH PRODUCTION, INC. Phone: (785) 483-9633

Proposed Plugging Method: Ordered out 330 sxs 60/40 pozmix - 10% gel - 700# hulls.  
D.V. at 1520' set with 300 sxs 50/50 pozmix.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/06/2002 10:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto 5 1/2" and mixed and pumped to capacity with 320 sxs cement and 700# hulls.  
Topped off with 10 sxs cement.

RECEIVED  
MAR 15 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

MAR 08 2002

Form CP-2/3

Mar 19 2002  
2002061534

FRANCIS C. STAAB ETAL  
 CATHERINE RT., MAYS, KS.

#1 BEFORT & WALDSCHMIDT

27-13-20W  
 330' FNL &  
 1120' FWL, NW

CONTR DRELLING OIL, INC. CTY ELLIS

GEOL \_\_\_\_\_ FIELD PLEASANT

E 2214 XE CR 2/13/76 CARD ISSUED 3/25/76 IP P 25 BOPD + WTR  
 LKC 3570-3514 O.A.

+	+	+
+	+	+

API 15-351-21,157

SMP	TOPS	DEPTH	DATUM
ANH	1522	+ 592	
B ANH	1568	+ 646	
TOP	3192	- 978	
LKC	3477	-1263	
ARB	3845	-1632	
RTD	3890	-1676	

8 5/8" 220/175sx, 5 1/2" 3889/175sx  
 OST (1) 3572-85/15-30-15-30, GTS/55"  
 TSTM, 940' OIL, 120' G&WCO, SIP 825-  
 825#, FP 327-393#  
 DST (2) 3593-97/30-30-30-30, 740' GIP,  
 60' OIL, 560' SW, SIP 576-575#, FP  
 262-262#  
 DST (3) 3658-67/30-30-30-30, 860' GIP,  
 30' HOCM, 125' G&OCW, 375' GCW, FSIP  
 812#, FP 262#  
 MICT - PF (CONG SD) 3813-17, 3836-40,  
 2823-27, NO FL, BP @ 3800, PF (LKC)  
 3612-14, 3570-14, 900' OIL/14HRS, SWB  
 5 BFPH (75% OIL)/4HRS, SWB 3 3/8 BFPH,  
 80% OIL/4HRS

INDEPENDENT OIL & GAS SERVICE