

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21216-00-00
Spot: SESWNW Sec/Twnshp/Rge: 27-13S-20W
3065 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: BEFORT-WALDSCHMIDT Well Number: 2
County: ELLIS Total Vertical Depth: 3692 feet

Operator License No.: 6892
Op Name: TRICH PRODUCTION, INC.
Address: PO BOX 1408 300 N. GREEN STREET ST
LONGVIEW, TX 75606

Conductor Pipe: Size _____ feet: _____
Surface Casing: Size 8.625 feet: 210 w/150 sxs cmt
Production: Size 4.5 feet: 1546 w/400 sxs cmt
Liner: Size _____ feet: _____

8/19.99

Well Type: SWD UIC Docket No: D19032.0 Date/Time to Plug: 03/06/2002 10:00 AM
Plug Co. License No.: 6892 Plug Co. Name: TRICH PRODUCTION, INC.
Proposal Rcvd. from: MIKE STANTON Company: TRICH PRODUCTION, INC. Phone: (785) 483-9633

Proposed Plugging Method: Ordered out 120 sxs 60/40 pozmix - 10% gel - 300# hulls.
Perfs at 1210' - 1230'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/06/2002 11:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto 4 1/2" - mixed and pumped to pressure with 120 sxs cement and 300# hulls.
Max. P.S.I. 1000#. S.I.P. 200#.

RECEIVED
MAR 15 2002
KCC WICHITA


Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

10/1

Signed _____



(TECHNICIAN)

MAR 13 2002

FILED
Mar 19-02
2002061534

BLACK-STEM INVESTORS OF HAYS
 CATHERINE ROUTE, HAYS, KS.

#2 BEFORT-WALDSCHMIDT

27-13-21
 425' FSL
 990' FWL

CONTR. DREILING OIL, INC. CTY. ELLIS

GEOL. _____ FIELD PLEASANT

2221 KB CM 2/26/76 CARD ISSUED 1/20/77 IP SWDW
CED HILLS

+	+
+	+
+	+

API 15-251-21,216

LOG	TOPS	DEPTH	DATUM
ANH	1529	+ 692	
TOP	3202	- 981	
HEEB	3450	-1229	
TOR	3470	-1249	
LANS	3492	-1271	
BKC	3749	-1528	
CONG	3820	-1599	
ARB NOT RECORDED			
TD	3892	-1671	

8-5/8" 210, 5 1/2" 1546
 DST (1) 3538-3556/30-30-30-30, 2100'
 GSY W, SIP 981-916# FP NA
 DST (2) 3572-3585/15-30-15-30, 120' GSY
 W TR W/OIL SPOTS, SIP 825-825# FP NA
 DST (3) 3589-3600/30-30-30-30, 620' GSY,
 OILY CW, (6% OIL) SIP 589-576#
 MICT - PF CED HILLS

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS