

4-110071

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-21,959-00-00  
100' N. & 100' W. of  
NW NW NE /4 SEC. 34, 13 S, 20 W  
5050 feet from S section line  
2410 feet from E section line

Operator license# 100

Lease: Storm Well # 5

Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13<sup>th</sup> Street  
Hays, Kansas 67601  
Control #200018-001

County: Ellis  
Well total depth 3830 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8<sup>5</sup>/<sub>8</sub> Inch @ 175 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Kansas Corporation Commission License# 100

Address: 2301 E. 13<sup>th</sup> Street - Hays, Kansas 67601

Company to plug at: Hour: 9:30 A.M. Day: 29 Month: October Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Ordered 315 sxs 60/40 pozmix and 600# hulls.  
Plug thru casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All  , Part  , None

Completed: Hour: 11:45 A.M., Day: 29, Month: October, Year: 1999

Actual plugging report: 8 5/8" set at 175' w/130 sxs. 5 1/2" casing at 3817' w/125 sxs.  
Alt II from 1520' to surface with 320 sxs. Tied to 8 5/8" S.P. Pressured to 750# Max.  
Took no cement. Tied to 5 1/2" casing - pumped 300 sxs cement with 600# hulls to 1000# Max.  
S.I.P. 400#. Total 300 sxs 60/40 pozmix with 10% gel and 600# hulls.  
Dakota at 485' - 785'.  
Anhydrite at 1515' - 1557'.  
Salt Section at 1891' - 2081'.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 16 1999  
11-16-99  
CONSERVATION DIVISION  
WICHITA KANSAS

Remarks: Allied Cementing. Werth Tank Service.  
Condition of casing (in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug (in place): YES  CALC  NO  Dakota plug: YES  NO   
Plugged through TUBING  CASING  Elevation: 2210 GL

I did  / did not  observe the plugging.

Roger Masis  
(agent)

100

2

JOHN B. COLLINS  
1007 CODY, SUITE A  
HAYS, KS 67601

REPLACEMENT CARD

34-13-20W


#5 STORM

230' FNL & 230' FWL NE/4

CONTR DREILING OIL, INC. CTY ELLIS

GEOL LAWRENCE F. GRAY FIELD PLEASANT

E 2215 KB CM 4/7/80 CARD ISSUED 8/21/80 IP OIL WELL  
2210 GL ARB OH 3817-3830



API 15-051-21,959

DL	TOPS	DEPTH	DATUM
ANH		1515	+ 700
B ANH		1557	+ 658
TOP		3137	- 922
HEEB		3443	-1228
TOR		3465	-1250
LKC		3485	-1270
BKC		3738	-1523
MARM		3773	-1558
ARB		3814	-1594
RTD		3830	-1615

8-5/8" 175/130sx, 5 1/2" 3817/125sx

NO DST'S  
MICT - CO, (ARB OH), AC 750 GAL,  
POP

INFO RELEASED: 4/30/81  
WAS OIL WELL - TIGHT HOLE

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS