

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21052-00-00  
Spot: CNENESW Sec/Twnshp/Rge: 34-13S-20W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: NICHOLSON TWIN Well Number: 4  
County: ELLIS Total Vertical Depth: 3885 feet

Operator License No.: 101  
Op Name: KCC FEE FUND  
Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 223  
Production: Size 5.5 feet: 3884  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/26/2001 2:30 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC  
Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE Phone: (785) 628-1747

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Plug with tubing.  
Perfs 750' - 1500' - 2000' - 2 shots per foot.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/26/2001 5:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 223' w/150 sxs. 5 1/2" casing at 3884' w/150 sxs.  
Ran tubing to 1824' - pumped 100 sxs cement and 200# hulls.  
Pulled tubing to 819' - circulated with 60 sxs cement and 300# hulls.  
Pulled all tubing and squeezed 15 sxs cement to Max. P.S.I. 250#. S.I.P. 250#.  
Total 175 sxs 60/40 pozmix - 10% gel and 500# hulls.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 5 2001  
CONSERVATION DIVISION

Remarks: SWIFT CEMENT COMPANY. WERTH TANK - WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses  
(TECHNICIAN)

J.B. COLLINS & J. BOYER

#4 NICHOLSON 'TWIN'

34-13-20W  
NE NE SW

1007 CODY, HAYS, KS.

CONTR RAINS & WILLIAMSON OIL CTY ELLIS

GEOL LAWRENCE GRAY

FIELD PLEASANT

W 2250 KB CM 5/6/75 <sup>CARD</sup> ISSUED 6/13/75 IP P 50 BOPD + 10% W  
LANS 3542-3700 OA

API 15-051-21,052

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		1555	+ 695
TOP		3223	- 973
HEEB		3471	-1221
TOR		3494	-1244
LANS		3512	-1262
BKC		3763	-1513
ARB		3840	-1590
TO		3885	-1635

8 5/8" 223/150sx, 5 1/2" 3884/150sx  
 DST (1) 3854-65/30-45-45-60, 60' OIL,  
 420' OCSW, SIP 1172-1162#, FP 102-  
 204#  
 MICT - PF (LKC) 3696-3700, 3674-78,  
 3542-48, A 3000, REC LD, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS