

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02902-00-00
Spot: CSESENW Sec/Twnshp/Rge: 34-13S-20W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: NICHOLSON W A Well Number: 3
County: ELLIS Total Vertical Depth: 3866 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 10.75 feet: 277
Production: Size 7 feet: 3863
Liner: Size 5.5 feet: 3863

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2001 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: DUANCE ACHTERBERG Company: FLATLAND MAINTENANCE Phone: (785) 628-1747

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug with tubing.
Perfs 750' - 1500' - 2240' - 2 shots per foot.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/26/2001 11:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

10 3/4" S.P. at 277'. 7" casing at 3863'. 5 1/2" liner at 3863'.
Ran tubing to 2014' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 1009' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 381' - pumped 75 sxs cement.
Pulled all tubing - topped off with 72 sxs cement.
Tied to 7" x 5 1/2" - took no cement. Max. P.S.I. 300#. S.I.P. 0#.
Tied to 10 3/4" x 7" annulus - pumped 40 sxs to Max. P.S.I. 250#. S.I.P. 250#.
Total 387 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 5 2001
CONSERVATION DIVISION

Remarks: SWIFT CEMENT COMPANY. WERTH TANK - WATER.

Plugged through: TBG

District: 04

10

Signed

Roger L. Moses

(TECHNICIAN)

TEXAS COMPANY

#3 W A NICHOLSON

34-13-20W
SE SE NW

Contr. POWELL DR LG

ELLIS County

E 2247 Comm. 8-12-55 Comp. 9-9-55

IP 180 BOPD &
331 BWPD

Tops	Depth	Datum
TOP	3225	-978
LANS	3513	-1266
ARB	3859	-1612
TD	3866	-1619

Casing
10" 277
7" 3863

CO TD: 12 B0 & 2 3/4 BW/
12 HR: TST .35 G0 & 15 GW/
LAST HR: SWB 124 B0 & 84
BW/9 HR: PMP 60 B0 & 111
B0/8 HR:

PLEASANT NORTH WEST POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS