

4-071138

15-051-05134-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 8-55

W2 NW SE /4 SEC. 34, 13 S, 20 W
1980 feet from S section line
2310 feet from E section line

Operator license# 30606

Lease Kingsley well # 2

Operator: Murfin Drilling Co., Inc.

County Ellis

Address: 250 North Water - Suite #300
Wichita, Kansas 67202
Stan Froetschner

Well total depth 3872 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feet

125.84

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Co Tools - Allied Cementing License# -

Address: Russell, Kansas 67665 - Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 28 Month: February Year: 95

Plugging proposal received from: Stan Froetschner

Company: Murfin Drilling Co., Inc. Phone: 316-267-3241

Were: 8 5/8" - 160' S.P. cwc. w/135 sxs. cement. 5 1/2" casing set at 3863' w/125 sxs. cement. 5 1/2" casing squeeze in 1958 @ 800' w/270 sxs. Perfs. 3520' - 3556'. Elv. 2257' - P.B.T.D. 3569'. Proposal 400 sxs 60/40 pozmix - 6% gel and 500# cotton seed hulls. Pump in with pump truck. Spot and displace all cement through tubing starting at 3539', also load or squeeze 5 1/2" x 8 5/8" annulus with cement - shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 5:45 P.M., Day: 28, Month: February, Year: 95

Actual plugging report: Murfin Drilling, Inc. ordered 400 sxs. 60/40 pozmix - 6% gel and 500# hulls. Pumped in with pump truck, spotted and displaced all cement through tubing.

- 1) 5 1/2" casing was squeezed in '58 @ 800' w/270 sxs. cement.
- 2) Perforate 5 1/2" casing at 2300' - 1450' - 860'.
- 3) 2 3/8" tubing at 3539' w/150 sxs.cmt. w/5 sxs. hulls added & displaced.
- 4) 2 3/8" tubing at 1519' w/125 sxs.cmt. - cmt. circ. out of 5 1/2" casing.
- 5) Squeezed 5 1/2" casing w/150 sxs. cmt. Max. P.S.I. 500#. (Allied returned for additional cement.
- 6) Squeezed 5 1/2" x 8 5/8" annulus w/115 sxs.cmt. Max. P.S.I. 100#.

Remarks: Cemented by Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING. Elevation: 2257 GL

I did [X] / did not [] observe the plugging.

Marion J. Schmidt
(agent)

RECEIVED STATE CORPORATION COMMISSION
MAR 13 1995
CONSERVATION DIVISION
WICHITA, KANSAS

42370
2-28