

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22387-00-00
Spot: NWSENW Sec/Twnshp/Rge: 34-13S-20W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: NICHOLSON Well Number: 6
County: ELLIS Total Vertical Depth: 3870 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 168
Production: Size 5.5 feet: 3868
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2001 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE Phone: (785) 628-1747

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs at 750' - 1500' - 2240' w/2 S.P.F.
Plug thru tubing.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/28/2001 2:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 168' w/185 sxs. 5 1/2" casing at 3868' w/150 sxs.
Ran tubing to 2014' - pumped 100 sxs cement and 200# hulls.
Pulled tubing to 1009' and circulated with 130 sxs cement and 300# hulls.
Pulled all tubing and topped off with 30 sxs cement.
8 5/8" x 5 1/2" annulus. Max. P.S.I. 300#. Took no cement.
Total of 260 sxs 60/40 pozmix -10% gel and 500# hulls.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 9 2001
CONSERVATION DIVISION

Remarks: SWIFT SERVICES, WERTH TANK - WATER.

Plugged through: TBG

District: 04

Signed _____

Roger L. Moses

(TECHNICIAN)

JUL 05 2001

JOHN B. COLLINS & JAY C. BOYER #6 NICHOLSON 34-13-20W
 1007 CODY #A, HAYS, KS 67601 NW SE NW
 CONTR DREILING OIL, INC. CTY ELLIS
 GEOL LAWRENCE F. GRAY FIELD PLEASANT
 E 2251 KB CM 4/23/81 CARD ISSUED 1/7/82 IP OIL WELL
 2246 GL ARB OH 3868-3870
 AM 15-051-22,387

| | | |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

| SMP | TOPS | DEPTH | DATUM |
|------|------|-------|-------|
| SC | | -1554 | + 697 |
| TOP | | 3232 | - 981 |
| HEEB | | 3480 | -1229 |
| TOR | | 3501 | -1250 |
| LANS | | 3519 | -1268 |
| B KC | | 3772 | -1521 |
| MARM | | 3815 | -1564 |
| ARB | | 3862 | -1611 |
| RTD | | 3870 | -1619 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

8 5/8" 168/185sx; 5 1/2" 3868/150sx
 NO DSTS REPORTED
 MICT - CO, ARB OH 3868-70, TSTD,
 POP, OIL WELL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS