

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22459-00-00  
Spot: CSWSENV Sec/Twnshp/Rge: 34-13S-20W  
2970 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: NICHOLSON Well Number: 7  
County: ELLIS Total Vertical Depth: 3881 feet

Operator License No.: 101  
Op Name: KCC FEE FUND  
Address: 130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 168  
Production: Size 5.5 feet: 3872  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2001 11:30 AM

Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC

Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE Phone: (785) 628-1747

Proposed Plugging Method: Ordered 350 sxs cement - 500# hulls.  
Perfs 730' - 1475' - 2220' - 2 shots per foot.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/26/2001 1:45 PM

KCC Agent: ROGER MOSES

**Actual Plugging Report:**

8 5/8" S.P. at 168' w/135 sxs cement. 5 1/2" casing at 3872' w/150 sxs cement.  
Ran tubing to 2014' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 1009' - circulated with 95 sxs cement and 300# hulls.  
Pulled all tubing and topped off with 52 sxs cement.  
Tied to 8 5/8" x 5 1/2" annulus - took no cement. Max. P.S.I. 300#. S.I.P. 0#.  
Total of 247 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 5 2001  
CONSERVATION DIVISION

Remarks: SWIFT CEMENT COMPANY, WERTH TANK- WATER.

Plugged through: TBG

District: 04

Signed

Roger B. Moses

(TECHNICIAN)

JUN 27 2001

JAY C. BOYER &  
JOHN B. COLLINS  
1007 CODY, SUITE A

REPLACEMENT CARD


34-13-20W  
SW SE NW

HAYS, KS. 67601  
CONTR. DREILING OIL, INC.

CTY. ELLIS

GEOL. LAWRENCE F. GRAY

FIELD PLEASANT



ELV 2263 KB SPD 6/19/81 CARD ISSUED 10/15/81 IP P 20 BOPD & WTR  
225B GL ARB OH 3872-3881  
API 15-051-22,459

SMP	Top	Depth/Datum
SC		1564+ 699
B/SC		1607+ 656
TOP		3247- 984
HEEB		3491-1228
TOR		3511-1248
LANS		3530-1267
BKC		3780-1517
MARM		3820-1557
ARB		3870-1607
RTD		3881-1618

8 5/8 " 168 / 135 SX, 5 1/2 " 3872 / 150 SX  
NO CORES OR DSTS  
MICT - CO. (ARB OH), ACIDIZED (AMT NA), SO, POP, P EST 20  
BOPD & WTR

INFO RELEASED: 2/26/87 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1987  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS