

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22564-00-00
Spot: NESWNW Sec/Twnshp/Rge: 34-13S-20W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: NICHOLSON Well Number: 2
County: ELLIS Total Vertical Depth: 3870 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 168
Production: Size 5.5 feet: 3864
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2001 8:00 AM

Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC

Proposal Rcvd. from: DUANE ACHTERBERG Company: EXPRESS WELL SERVICE INC Phone: (785) 628-1747

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs at 750' - 1500' - 2240' w/2 S.P.F.
Plug with tubing.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/28/2001 10:30 AM

KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 168' w/135 sxs. 5 1/2" casing at 3864' w/150 sxs.
Ran tubing to 2014' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1009' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 381' and circulated with 40 sxs cement.
Pulled all tubing and topped off with 30 sxs cement.
Tied to 8 5/8" x 5 1/2" annulus. Max. P.S.I. 300#. Took no cement.
Total of 270 sxs 60/40 pozmix with 10% gel and 500# hulls.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 9 2001

CONSERVATION DIVISION

Remarks: SWIFT SERVICES. WERTH TANK - WATER.

Plugged through: TBG

District: 04

Signed _____

Roger L. Moses

(TECHNICIAN)

JOHN B. COLLINS &
JAY C. BOYER
1007 CODY, SUITE A

REPLACEMENT CARD

34-13-20W
NE SW NW


HAYS, KS, 67601
CONTR' DREILING OIL, INC.

#9 NICHOLSON

CTY ELLIS

GEOL LAWRENCE F. GRAY

FIELD PLEASANT



ELV 2244 KB SPD 8/14/81 CARD ISSUED 11/12/81 IP P 20 BOPD & WTR
2239 GL ARB OH 3864-3870
API 15-051-22,564

SMP	Tops	Depth/Datum
SC		1553+ 691
B/SC		1592+ 652
TOP		3231+ 987
HEEB		3478-1234
TOR		3501-1257
LANS		3518-1274
BKC		3768-1524
MARM		3812-1568
ARB		3858-1614
RTD		3870-1626

8 5/8 " 168 / 135 SX, 5 1/2 " 3864 / 150 SX
NO CORES OR DSTS
MCT - CO, (ARB OH), ACIDIZED (AMT NA), GSO, POP, P EST 20
BOPD & WTR

INFO RELEASED: 2/26/87 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS