

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22543-00-00
Spot: CSESWNW Sec/Twnshp/Rge: 34-13S-20W
2970 feet from S Section Line, 4260 feet from E Section Line
Lease/Unit Name: NICHOLSON Well Number: 8
County: ELLIS Total Vertical Depth: 3874 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 135 w/135 sxs cmt
Production: Size 5.5 feet: 3868 w/150 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/25/2001 1:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE Phone: (785) 628-1747

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/25/2001 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 2250' - 1500' - 760'.
Tied onto and pumped 275 sxs with 500# hulls.
Max. P.S.I. 400#. S.I.P. 250#.
Annulus instant pressure.
06-26- 2001 - Topped with 28 sxs.

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 29 2001


CONSERVATION DIVISION

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04


Signed



(TECHNICIAN)

JUN 27 2001

JOHN B. COLLINS & REPLACEMENT CARD 34-13-20W
 JAY C. BOYER #8 NICHOLSON SE SW NW
 1007 CODY, SUITE A
 HAYS, KS, 67601
 CONTR DRELLING OIL, INC. CTY ELLIS
 GEOL LAWRENCE E. GRAY FIELD PLEASANT



ELV 2253 KB SPD 7/28/81 CARD ISSUED 10/15/81 IP P. 20 BOPD & WTR
 2248 GL ARB OH 3868-3874
 API 15-051-22,543

LOG	Tops	Depth/Datum
SC	1556+ 697
B/SC	1602+ 651
TOP	3240- 987
HEEB	3487-1234
TOR	3508-1255
LANS	3525-1272
BKC	3773-1520
MARM	3818-1565
ARB	3862-1609
RTD	3874-1621

8 5/8 " 165 / 135 SX, 5 1/2 " 3868 / 150 SX
 NO CORES OR DSTS
 MICT - CO. (ARB OH), ACIDIZED (AMT NA), SO, POP, P EST 20
 BOPD & WTR

INFO RELEASED: 2/26/87 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1987
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS