

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22351-00-00
Spot: CNESENW Sec/Twnshp/Rge: 34-13S-20W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: NICHOLSON Well Number: 5
County: ELLIS Total Vertical Depth: 3842 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 167 w/130 sxs cmt
Production: Size 5.5 feet: 3833 w/150 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/25/2001 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE Phone: (785) 628-1747

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/25/2001 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 2250' - 1500' - 760'.
RIH with tubing to 2014' - tied onto and pumped 100 sxs with 500# hulls. -
Pulled to 1009' and spotted 100 sxs cement.
Pulled to 500' and circulated cement with 40 sxs.
POOH and topped with 15 sxs.
Annulus 400# instant shut in.
06-26-2001 - Topped with 12 sxs.


RECEIVED
KANSAS CORPORATION COMMISSION
JUN 29 2001
CONSERVATION DIVISION

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

REPLACEMENT CARD

JOHN B. COLLINS &
JAY C. BOYER
1007 CODY, SUITE A

#5 NICHOLSON


34-13-20W
NE SE NW

HAYS, KS 67601
CONTR DRELLING OIL, INC.

CTY ELLIS

GEOLOGIST LAWRENCE F. GRAY

FIELD PLEASANT



ELV 2233 KB SPD 3/30/81 CARD ISSUED 6/18/81 IP P 20 BOPD & WTR
2228 GL ARB OH 3833-3842
API 15-051-22,351

SMP	Tops	Depth/Datum
SC	1531 + 702
TOP	3208 - 975
HEEB	3460 - 1227
TOR	3479 - 1246
LANS	3498 - 1265
BKC	3751 - 1518
MARM	3794 - 1561
ARB	3828 - 1595
RTD	3842 - 1609

8 5/8 " 167 / 130 SX, 5 1/2 " 3833 / 150 SX
NO CORES OR DSTS
MIST - CO. (ARB OH), ACIDIZED (AMT NA), SO, POP, P EST 20
BOPD & WTR

INFO RELEASED: 2/26/87 - WAS OIL WELL - TIGHT HOLE
SPD 3/30/81