

4-041449

051-20,670-00-00

86  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- 11-17-70

82 NW NE /4 SEC. 34 , 13 S, 20 W  
4290 feet from S section line  
1980 feet from E section line

Operator license# 3613 Lease Storm well # 2

Operator: Hallwood Petroleum, Inc. County Ellis 124.67

Address: 4582 S. Ulster St. Pkwy. Well total depth 3836 feet  
Suite 1700 Conductor Pipe: 0 inch @ 0 feet  
Denver, Colorado 80237 Surface pipe 8 5/8 Inch @ 206 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#           

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 24 Month: March Year: 93

Plugging proposal received from: Aven Weaverling

Company: Hallwood Petroleum, Inc. Phone:           

Were: 5 1/2" casing set @ 3829' w/150 sx. cement. Perf. @ 3410'-3697'  
Squeezed at 745' w/150 sx. Anhy. - Perf. @ 1530'.  
Ordered 300 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls  
and 12 sx. gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 1:30P.M., Day: 24, Month: March, Year: 93

Actual plugging report: R.I.H. with tubing to 3820', spot 75 sx. cement  
with 300# hulls with T.O.C. at 3200'. Pulled up 3200', spot 12 sx.  
gel. Pulled tubing to 1540', spot 100 sx. cement with 100# hulls to  
circulate to surface. P.O.O.H. with tubing. Hooked-up to 5 1/2" casing,  
squeezed 25 sx. cement. Max. 500# P.S.I. S.I. 300#. Hooked-up to  
8' 5/8" surface pipe, squeezed 60 sxs. cement. Max. 400# P.S.I.  
S.I. 300#.

Remarks:           

Condition of casing(in hole):GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  NO  RECEIVED  
Plugged through TUBING  , CASING  . Elevation:            STATE CORPORATION COMMISSION

I did[  ] / did not[  ] observe the plugging.

Dennis L. Hamel APR 6 1993

JATF . 4-8-93  
37556  
3-24

(agent) 04-06-93  
CONSERVATION DIVISION  
Form CP-2/3 Wichita, Kansas