

To: 6 070566
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-24-317-00-00

SE SE SW, SEC. 34, T 13 S, R 20 W/8

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Nicholson Well # 1-34

Operator: Murfin Drilling Co.

County Ellis 129.35

Name: _____

Address 250 N. Water # 300

Well Total Depth 3980 feet

Wichita, Kansas 67202

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8" feet 296

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing Co. License Number _____

Address 1100 E. 8th, Hays, Kansas 67601

Company to plug at: Hour: 10:00 AM Day: 18 Month: June Year: 19 87

Plugging proposal received from Stan Foroctschner

(company name) Murfin Drilling Co. (phone) 316-267-3241

were: 8 5/8" - 296' S.P. Cuc with 190 sk cmt, 5 1/2" csg set at 3979 ft. with 150' sk cmt.

D.V. tool at 1670 ft cuc with 350 sk cmt, Perfs. 3909' to 3896', no pipe recovery.

Proposal - 200 sk 65/35 pozmix, 10% gel, 2% additive, (Econolite) and 5 sk hulls

pump in 8 5/8" S.P. with pump truck, pump in 10 sk cement

90 sk cement with 4 sk Hulls mixed in, and then 100 sk cement. Also load and pressure annulus with cement. Shut in under pressure

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 AM Day: 18 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Ordered 200 sk 65/35 pozmix, 10 % gel, 2% Additive, (Econolite) and 5 sk hulls.

Pumped in with pump truck, 10 sk cement, then 90 sk cement with 4 sk hulls added in, then 100 sk cement with 1 sk hulls added in. Max. Pressure 800 PSIG shut in pressure

600 PSIG In annulus pumped in 7 sk cement Max. PSIG 325 shut in at 325 PSIG.

Cemented by Halliburton Cmt. Return check June 23, 1987 on cement plug. Showed plug down 10 ft.

Remarks: 6-24-87

(If additional description is necessary, use BACK of this form.)

I (and XEROX) observe this plugging.

07-10-87
JUL 10 1987

DATE 7-13-87

Signed Marion J. Schmidt (TECHNICIAN)

INV. NO. 17479

Wichita, Kansas Marion J. Schmidt