

4-090555

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 7-15-74

N2 NE SW / 4 SEC. 25, 13 S, 20 W
2310 feet from S section line
3300 feet from E section line

Operator license# 3134

Lease Orth OWWO Well # 4

Operator: GLM Company

County: Ellis

Address: P.O. Box 193
Russell, Kansas 67665

Well total depth 3887 ^{126.5} feet
 Conductor Pipe: 0 inch @ 0 feet
 Surface pipe 8 5/8 Inch @ 254 feet

Aband. oil well X, Gas well____, Input well____, SWD____, D & A____

Plugging contractor: Co Tools License# -

Address: _____

Company to plug at: Hour: 8:30 A.M. Day: 30 Month: December Year: 1996

Plugging proposal received from: Lloyd Davis

Company: GLM Company

Phone: 913-483-6220

Were: Order 350 sxs 60/40 posmix - 10% gel - hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[☒], Part[☐], None[☐]

Completed: Hour: 12:00 P.M., Day: 30, Month: December, Year: 1996

Actual plugging report: 8 5/8" to 254' w/150 sxs. 5 1/2" to 3886' w/140 sxs. Perfs at 3625' - 3674'. Perforated at 2075' - 1515' - 800'. Ran tubing to 2100' and pumped 100 sxs cement with 300# hulls. Pulled tubing to 1000' and pumped 70 sxs cement with 200# hulls. Cement circulated. Pulled tubing and tied onto 5 1/2" casing and pumped 30 sxs cement with 100# hulls. Max. P.S.I 800#. S.I.P 450#. Backside cement to surface.

Remarks: Allied Cementing. Log Tech of Hays.

Condition of casing(in hole): GOOD BAD **X** Anhy.plugin: YES **X** NO

Bottom plug(in place): YES___, CALC X, NO___ **Dakota plug:** YES X, NO___

Plugged through TUBING X, CASING . Elevation: 2202 R.B. GL

I did[x'] / did not[] observe the plugging.

Ed Achenbach
(agent)

Form CP-2/3

JAN 06 1997

47272

12. 1. 1948 : 1. 1. 1948