

4- 020084

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15-051-22,992-0000

SW SW NW /4 SEC. 35 , 13 S, 20 W
2970 feet from S section line
4950 feet from E section line

Operator license# 09067

Lease: Storm Well # 1

Operator: DaMar Resources, Inc.
Address: P.O. Box 70
Hays, Kansas 67601

County: Ellis 126.75
Well total depth 3900 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 3/4 Inch @ 342 feet

Aband. oil well X , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing, Inc. License# 09325

Address: Russell, Kansas

Company to plug at: Hour: _____ Day: 05 Month: December Year: 1995

Plugging proposal received from: Curtis R. Longpine

Company: _____ Phone: 625-0020

Were: 8 3/4" Surface casing set @ 342' w/200 sx cement (est.); 5 1/2" Production casing set @ 3900' w/200 sx cement (est.) (two-staged to surface); Total Depth: 3900'; Plug Back Total Depth (Bridge Plug): 3710; Perforations: 3689-91, 3665-69, 3581-85, 3557-60, 3515-19, 3215-20; Elevation: 2220 G.L., 2230 K.B.; Anhydrite Depth: 1532-70; Dakota: 495 - 795; Salt Section: 1930 - 2120;

Used 180 sx 60/40 pozmix, 10% gel cement w/400# hulls, w/18 sx gel.

Plugging Proposal Received by: Herb Deines / Ken Kuhn

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00 AM , Day: 05 , Month: December , Year: 1995

Actual plugging report: Connected to backside, pumping initiated immediate pressure rise to 500#s; Connected to top of casing and pumped 40 sx cement w/300#s hulls, pumped 18 sx gel, pumped 140 sx cement w/100#s hulls.

Maximum pump press: 600#s

Static pressure: 200#s

Completion time: 11:00 AM

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 08 1995
12-8-95

CONSERVATION DIVISION
WICHITA, KS

Remarks: Allied Cementing performed the cement job.

Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____

Bottom plug(in place): YES _____, CALC X, NO _____ Dakota plug: YES X, NO _____

Plugged through TUBING _____, CASING X. Elevation: 2220 GL

I did not / did npt[] observe the plugging.

[Signature]
(agent)
Form CP-2/3

DATE 12-13-95
44329