

4-071148

15-051-20671-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 10-17-67

C SE NW /4 SEC. 35, 13 S, 20 W
3300 feet from S section line
3300 feet from E section line

Operator license# 9292

Lease: Storm Well # 4

Operator: Scheck Oil Operations

County: Ellis

Address: 225 Main Street
Russell, Kansas 67665
Tim Scheck

Well total depth 3837 124.70 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 257 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 3 Month: October Year: 1995

Plugging proposal received from: Tim Scheck

Company: Scheck Oil Operations Phone: 913-483-3404

Were: 8 5/8" - 257' S.P. cwc. w/175 sxs cement. 5 1/2" casing set at 3837' w/150 sxs cement. D.V. tool at 1583' cwc w/N/A sxs cement. Static fluid 1085'. T.D. at 3837' - Elv. 2184' - Anhy. 1515'. Proposal by Dennis Hamel, K.C.C. - District #4 - 200 sxs 60/40 pozmix - 10% gel and 500# hulls. Pump in with pump truck. Pump in 5 1/2" casing - pump in 25 sxs cement with 2 sxs hulls - followed with 12 sxs Bentonite gel then 150 sxs cement. Shut in under pressure. Squeeze 5 1/2" x 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:30 P.M. Day: 3 Month: October Year: 1995

Actual plugging report: Allied Cement brought 245 sxs 60/40 pozmix - 10% gel - 12 sxs Bentonite gel - 500# of cotton seed hulls. Pumped in with pump truck.

1) Squeezed 5 1/2" x 8 5/8" annulus with 40 sxs cement with 1 sx hulls. Max. P.S.I. 400#. S.I.P. 200#.

2) Pumped in 5 1/2" casing with 25 sxs cement with 1 sx hulls followed with 12 sxs Bentonite gel, then 180 sxs cement with 2 sxs hulls. Max. P.S.I. 800#. S.I.P. 200#.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Cemented by Allied Cementing - Russell, Kansas 67665

OCT 13 1995
10-13-95

Condition of casing(in hole): GOOD X BAD

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING X Elevation: 2184 GL

I, did not observe the plugging.

Marion J. Schmidt
(agent)

DATE: 10-26-95

INV. NO. 42861

10-3