

4-060561

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-21,606-0000
100' SW
SW NW SW /4 SEC. 35, 13 S, 20 W
1550 feet from S section line
4950 feet from E section line

Operator license# 30606 Lease Dreiling well # 1

Operator: Murfin Drilling Co., Inc. County Ellis

Address: 250 N. Water Well total depth 3940 feet ^{128.05}
Suite #300 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 261 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 1:00P.M. Day: 16 Month: August Year: 94

Plugging proposal received from: Mike

Company: Murfin Drilling Co., Inc. Phone: 316-267-3241

Were: Order 250 sx. 60/40 posmix - 10% gel and hulls.
Perforate and run tubing to plug. - Arbuckle producer.
Squeeze at 1300' with 300 sx.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:00P.M., Day: 16, Month: August, Year: 94

Actual plugging report: 8 5/8" to 261'. 5 1/2" to 3939'. Perf. at
800' - 1525' - 2100'. Ran tubing to 2500'. Pumped 90 sx. cement with
250# hulls. Pulled tubing to 1250' and circulated cement to surface
with 60 sx. cement. Tied onto annulus with instant 500# S.I.P.
Tied onto production casing and pumped 60 sx. cement. Max. 1000#.
S.I.P. 700#.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X NO
Plugged through TUBING X, CASING . Elevation: 2213

I did not [X] observe the plugging.

DATE 9-5-94
WV. NO. 41089

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1994
8-23-94
CONSERVATION DIVISION
WICHITA, KANSAS

DH (agent)
Form CP-2/3