

4-060355

43R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-051-21,262-00-01

NW NW NW /4 SEC. 35, 13 S, 20 W  
4950 feet from S section line  
4950 feet from E section line

Operator license# 9292

Lease Storm well # 3

Operator: Scheck Oil

County Ellis

Address: 225 Main  
Russell, Kansas 67665

Well total depth 3866 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 205 feet

125.65

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: P.O. Box 347, Chase, Kansas 67524

Company to plug at: Hour: 11:00A.M Day: 3 Month: November Year: 92

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pulling, Inc. Phone: 316-938-2943

Were: Order 350 sxs. 65/35 posmix - 8% gel. and hulls.  
Well two staged.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 1:30P.M., Day: 3, Month: November, Year: 92

Actual plugging report: 8 5/8" to 205'. 5 1/2" to 3864'. Tied onto production casing and pumped 270 sxs. cement with 350# hulls.

Max. 700#. S.I.P. 300#. Tied onto annulus and pumped 65 sxs. cement with 50# hulls. Max. 500#. S.I.P. 200#.

RECEIVED  
STATE CORPORATION COMMISSION

11-16-92  
NOV 16 1992

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD      Any plug: YES X NO     

Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X NO     

Plugged through TUBING     , CASING X. Elevation: 2219 CL     

I did X / did not [      ] observe the plugging.

*Bill Deines*  
E.A.D.

(agent)

Form CP-2/3

INVOICED  
12-4-92  
36966