

4-071149

15-051-19429-00-00

D-26,218

API Number: 15- - 10-17-67

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NE NE NW /4 SEC. 35, 13 S, 20 W  
4950 feet from S section line  
2970 feet from E section line

Operator license# 9292

Lease: Storm Well # 2

Operator: Scheck Oil Operations

County: Ellis

Address: 225 Main Street  
Russell, Kansas 67665  
Tim Scheck

Well total depth original 3883 126.20 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 235 feet

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Allied Cementing Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 3 Month: October Year: 1995

Plugging proposal received from: Tim Scheck

Company: Scheck Oil Operations Phone: 913-483-3404

Were: 8 5/8" - 235' S.P. cwc. w/150 sxs cement. 5 1/2" casing set at 3883' w/150 sxs cement. D.V. tool at 1475' cwc w/N/A sxs cement - also 5 1/2" packer set at 1071'. Original T.D. 3883' - plug back at 1475'. Elev. 2172' - perfs 11:00 - 12:00. Proposal by Dennis Hamel K.C.C. District #4. Ordered 125 sxs 60/40 pozmix - 10% gel and 200# cotton seed hulls. Pump in with pump truck - load 5 1/2" casing from top to bottom with cement. Shut in under pressure, also squeeze 5 1/2" x 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 11:45 A.M. Day: 3 Month: October Year: 1995

Actual plugging report: Scheck Oil ordered 125 sxs 60/40 pozmix - 10% gel - 200# of cotton seed hulls. Pumped in with pump truck.

- 1) Pumped 110 sxs cement with 2 sxs hulls in 5 1/2" casing. Max. P.S.I. 1000#. S.I.P. 1500#.
- 2) Annulus 5 1/2" x 8 5/8" - cement visable at surface.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1995

10-13-95

Remarks: Cemented by Allied Cementing - Russell, Kansas 67665 CONSERVATION DIVISION

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES Wichita, Kansas NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING X Elevation: 2172 GL

INVOICE I did not observe the plugging.

*inferno schmidt*  
(agent)

DATE: 10-26-95

NO. 43862