

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23481-00-00  
Spot: CNWISESE Sec/Twnshp/Rge: 25-13S-20W  
990 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: YOUNGER Well Number: 10-L  
County: ELLIS Total Vertical Depth: 3810 feet

Operator License No.: 30680 Conductor Pipe: Size \_\_\_\_\_ feet: 8 1/23.83  
Op Name: GEIST, WILLIAM DBA GEIST OIL OPERA Surface Casing: Size 8.625 feet: 163 w/110 sxs cmt  
Address: 807 GRANT RR 2 Production: Size 5.5 feet: 3807  
VICTORIA, KS 67671 Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/29/2002 2:00 PM  
Plug Co. License No.: 30680 Plug Co. Name: GEIST, WILLIAM DBA GEIST OIL OPERATIONS  
Proposal Rcvd. from: BILL GEIST Company: GEIST, WILLIAM DBA GEIST OIL O Phone: (785) 735-2664

Proposed Plugging Method: Ordered out 195 sxs 60/40 pozmix - 20 sxs gel - 500# hulls.  
Emergency plug. D.V. at 1480'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/29/2002 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Hooked onto annulus - instant pressure.  
Switched over to 5 1/2" - mixed and pumped 40 sxs cement with 500# hulls, followed by 20 sxs gel and topped off with 145 sxs cement.  
Max. P.S.I. 1000#. S.I.P. 700#.

RECEIVED  
APR 05 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.


Plugged through: CSG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

PD.




Form CP-2/3

APR 02 2002

4-08-02  
2002061623

JOHN B. COLLINS  
 1007 CODY, SUITE A #10 "L" YOUNGER 25-13-20W  
 HAYS, KS 67601 NW SE SE  
 CONTR DREILING OIL, INC. CTY ELLIS  
 GEOL LARRY GRAY FIELD IRVIN  
 ELV 2192 KB SPD 5/31/83 CARD ISSUED 8/18/83 IP OIL WELL  
 API 15-051-23,481 ARB OH 3807-3810



SMP	Tops	Depth-Datum	
			8 5/8" 163/110SX; 5 1/2 " 3807
			NO DST'S
			MICT - CO, (ARB OH), AC 500G; SWB DWN, SO, POP
ANH	.....	1476 + 716	
TOP	.....	3186 - 994	
HEEB	.....	3430 - 1238	
TOR	.....	3454 - 1262	
LANS	.....	3474 - 1282	
BKC	.....	3722 - 1530	
PENN CONG	.....	3758 - 1566	
ARB	.....	3805 - 1613	
RTD	.....	3810 - 1618	