



KANSAS CORPORATION COMMISSION 1056919
OIL & GAS CONSERVATION DIVISION

Form ACO-1

June 2009

Form Must Be Typed

Form must be Signed

All blanks must be Filled

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

OPERATOR: License # 3895
Name: Bobcat Oilfield Services, Inc.
Address 1: 30805 COLD WATER RD
Address 2: _____
City: LOUISBURG State: KS Zip: 66053 + 8108
Contact Person: Bob Eberhart
Phone: (913) 285-0873
CONTRACTOR: License # 4339
Name: Jackson, Dale E & Sue Ellen dba Dale E. Jackson Production Co.
Wellsite Geologist: N/A
Purchaser: High Sierra Crude Oil

Designate Type of Completion:

- ☒ New Well ☐ Re-Entry ☐ Workover
- ☐ Oil ☐ WSW ☐ SWD ☐ SIOW
☐ Gas ☐ D&A ☒ ENHR ☐ SIGW
☐ OG ☐ GSW ☐ Temp. Abd.
☐ CM (Coal Bed Methane)
☐ Cathodic ☐ Other (Core, Expl., etc.): _____

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
☐ Deepening ☐ Re-perf. ☐ Conv. to ENHR ☐ Conv. to SWD
☐ Conv. to GSW
☐ Plug Back: _____ Plug Back Total Depth: _____
☐ Commingled Permit #: _____
☐ Dual Completion Permit #: _____
☐ SWD Permit #: _____
☐ ENHR Permit #: _____
☐ GSW Permit #: _____

5/6/2011 5/9/2011 6/24/2011
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 15-107-24360-00-00

Spot Description: _____
NE NE NW SE Sec. 5 Twp. 20 S. R. 23 ☒ East ☐ West
2335 Feet from ☐ North / ☒ South Line of Section
1347 Feet from ☒ East / ☐ West Line of Section

Footages Calculated from Nearest Outside Section Corner:

☐ NE ☐ NW ☒ SE ☐ SW

County: Linn

Lease Name: NE Baker Well #: C-13

Field Name: LaCygne-Cadmus

Producing Formation: Peru

Elevation: Ground: 919 Kelly Bushing: 0

Total Depth: 343 Plug Back Total Depth: _____

Amount of Surface Pipe Set and Cemented at: 20 Feet

Multiple Stage Cementing Collar Used? ☐ Yes ☒ No

If yes, show depth set: _____ Feet

If Alternate II completion, cement circulated from: 338
feet depth to: 0 w/ 50 sx cmt.

Drilling Fluid Management Plan

(Data must be collected from the Reserve Pit)

Chloride content: _____ ppm Fluid volume: _____ bbls

Dewatering method used: _____

Location of fluid disposal if hauled offsite: _____

Operator Name: _____

Lease Name: _____ License #: _____

Quarter _____ Sec. _____ Twp. _____ S. R. _____ ☐ East ☐ West

County: _____ Permit #: _____

AFFIDAVIT

I am the affiant and I hereby certify that all requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Submitted Electronically

KCC Office Use ONLY

- ☐ Letter of Confidentiality Received
Date: _____
☐ Confidential Release Date: _____
☒ Wireline Log Received
☐ Geologist Report Received
☒ UIC Distribution
ALT ☐ I ☒ II ☐ III Approved by: Deanna Gantner Date: 06/28/2011



1056919

Operator Name: Bobcat Oilfield Services, Inc. Lease Name: NE Baker Well #: C-13
 Sec. 5 Twp. 20 S. R. 23 ☒ East ☐ West County: Linn

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach complete copy of all Electric Wire-line Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken ☐ Yes ☒ No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey ☐ Yes ☒ No Cores Taken ☒ Yes ☐ No Electric Log Run ☒ Yes ☐ No Electric Log Submitted Electronically ☒ Yes ☐ No <i>(If no, Submit Copy)</i> List All E. Logs Run: Gamma Ray/Neutron/CCL	☒ Log Formation (Top), Depth and Datum ☐ Sample <table style="width: 100%;"> <tr> <td style="width: 60%;">Name</td> <td style="width: 20%;">Top</td> <td style="width: 20%;">Datum</td> </tr> <tr> <td>Peru</td> <td>270</td> <td>GL</td> </tr> </table>	Name	Top	Datum	Peru	270	GL
Name	Top	Datum					
Peru	270	GL					

CASING RECORD ☐ New ☒ Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface casing	8.75	6.25	8	20	Portland	5	
Production casing	5.625	2.875	6	338	Portland/Fly Ash	50	60/40 Poz Mix

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	# Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing				
___ Plug Back TD				
___ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
3	273-280	Acid 500 gal 7.5% HCL	
3	283-292		

TUBING RECORD:		Size:	Set At:	Packer At:	Liner Run: ☐ Yes ☐ No
Date of First, Resumed Production, SWD or ENHR.			Producing Method: ☐ Flowing ☐ Pumping ☐ Gas Lift ☐ Other (Explain) _____		
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

DISPOSITION OF GAS: ☐ Vented ☐ Sold ☐ Used on Lease <i>(If vented, Submit ACO-18.)</i>	METHOD OF COMPLETION: ☐ Open Hole ☒ Perf. ☐ Dually Comp. ☐ Commingled <i>(Submit ACO-5)</i> <i>(Submit ACO-4)</i> ☐ Other (Specify) _____	PRODUCTION INTERVAL: _____ _____
--	---	---

Lease:	NORTH EAST BAKER	
Owner:	BOBCAT OILFIELD SERVICES	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	
Surface:	Cemented:	Hole Size:
20FT, 6IN	5 SACKS	8 3/4
Longstring	Cemented:	Hole Size:
338' 2	50	5 5/8
7/8" 8RD		

Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

Well #: C-13
Location: N2,N2,N2-SE-S5-T20-R23E
County: UNN
FSL: 3825 2335
FEL: 4320 1347
API#: 15-107-24360-00-00
Started: 5-6-11
Completed: 5-9-11

SN: NONE	Packer:	TD: 343'
Plugged:	Bottom Plug:	

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	TOP SOIL			
4	5	CLAY			SURFACE 5-6-11
16	20	LIME			SET TIME 4:30 P.M.
4	24	SHALE			CALLED 12:30 P.M. BECKY
3	27	BLACK SHALE			
72	49	LIME			
3	52	SHALE			LONGSTRING 338' 2 7/8" 8RD PIPE TD343'
1	53	BLACK SHALE			SET TIME 1:30P.M. 5-9-11
13	66	LIME (SHALEY)			CALLED 12:00P.M. MIKE
1	67	BLACK SHALE			
10	77	SHALE(LIMEY)			
33	110	SHALE			
13	125	SANDY SHALE (DRY SAND)			
93	218	SHALE			
1	219	BLACK SHALE			
6	225	SHALE			
6	231	LIME			
4	235	SHALE			
2	237	RED BED			
15	252	SHALE			
1	253	LIME			
5	258	SHALE			
8	266	LIME			
3.5	269.5	SANDY SHALE			
4	273.5	OIL SAND (SHALEY)(POOR BLEED)			
6.5	280	OIL SAND (SOME SHALE)(GOOD BLEED)(LITTLE SHOW OF WATER)			
.5	280.5	SANDY SHALE			
1.5	282	OIL SAND (VERY SHALEY)(FRACTURED)(POOR BLEED)			
3	285	SANDY SHALE (SOME OIL SAND STREAKY)(POOR BLEED)			
2	287	OIL SAND (SHALEY)(GOOD BLEED)			
1	288	SANDY SHALE(SOME OIL SAND STREAKS) (POOR BLEED)			
1	289	OIL SAND (SHALEY)(GOOD BLEED)			
1	290	OIL SAND SOME SHALE (GOOD BLEED)			
1.5	291.5	LIME (OIL SATURATED)(GOOD BLEED)(DID NOT BLEED UNTIL AFTER CORE BROKEN)			
8.5	300	SANDY SHALE (SOME OIL)SAND STREAK PBLEED			
12	312	SHALE			
2	314	COAL			
4	318	SHALE			
11	329	LIME			
8	337	SHALE			
TD	343	LIME			



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 913-795-2991

Well #: C-13
Location: N2, N2, N2-SE-SS-T20-R23E
County: LINN
FSL: 2325
FEL: 1320
API#: 15-107-24360-00-00
Started: 5-6-11
Completed: 5-9-11

Lease:	NORTH EAST BAKER
Owner:	BOBCAT OILFIELD SERVICES INC.
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Core Run #1

FT	Depth	Clock	Time	Formation/Remarks	Depth
0	272				
1	273		1	OIL SAND (SHALEY (POOR BLEED)	273.5
2	274		1		
3	275		.5		
4	276		.5		
5	277		1		
6	278		3/4		
7	279		1	OIL SAND (SOME SHALE)(GOOD BLEED) LITTLE SHOW OF WATER	280
8	280		1		
9	281		1	SANDY SHALE	280.5
10	282		1.5	OIL SAND (VERY SHALEY (FRACTURED POOR BLEED)	282
11	283		3.5		
12	284		1		
13	285		1	SANDY SHALE(SOME OIL SAND STREAKS) (POOR BLEED)	285
14	286		.5		
15	287		1	OIL SAND (SHALEY)(GOOD BLEED)	287.5
16	289		1	SANDY SHALE (SOME OIL SAND STREAK)(POOR BLEED)	288
17	290		1.5	OIL SAND (SHALEY)(GOOD BLEED)	289
18	291		1	OIL SAND (SOME SHALE)(GOOD BLEED)	290
19	292		1.5	LIME (OIL SATURATED) (GOOD BLEED) (DID NOT BLEED UNTIL AFTER CORE BROKE)	291.5
20			2		
				SANDY SHALE (SOME OIL SAND STREAK)(POOR BLEED)	

