

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5004
Name: Vincent Oil Corporation
Address 1: 155 N. Market, Ste 700
Address 2: _____
City: Wichita State: Kansas Zip: 67202 + 1821
Contact Person: M.L. Korphage
Phone: (316) 682-9464
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. 5075'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 097-20036-00-08 ⁰¹ ^{KCC}
Spot Description: SE-NE
_____ SE-NE Sec. 7 Twp. 30 S. R. 18 East West
1,980 Feet from North / South Line of Section
660 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kiowa
Lease Name: Parkin "C" Well #: 1 (OWWO)
Date Well Completed: 2/10/1984
The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 2/16/2010
Plugging Completed: 2/18/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	429'	None
		Production	4 1/2"	5075'	2600'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2/16/2010: Unseated pump, pulled rods and tubing
2/17/2010: Pumped 80 bbls lease water down 4 1/2" casing to kill well; prepared wellhead to plug; pumped 30 sx cement and 200# hulls down 4 1/2" casing; displaced with 73 bbls of water; SDFN
2/18/2010: Tagged cement at 4700', ripped csg 22840' & 2600', pulled up to 1180'; pumped 15 sx gel, 50 sx cmt. (3% CC), and 100# hulls; pulled up to 450', pumped 50 sx cmt and 100# hulls; pulled up to 40'; pumped 20 sx cmt to surface. Plugging complete. Used total of 150 sx 60/40 Poz (4% Gel) - Quality Oilwell Cementing Ticket #3995


Plugging Contractor License #: 31925 Name: Quality Well Service
Address 1: 190 th US 56 Highway Address 2: _____
City: Ellinwood State: Kansas Zip: 67526 + _____
Phone: (620) 727-3410
Name of Party Responsible for Plugging Fees: Vincent Oil Corporation
State of Kansas County, Sedgwick, ss.
M.L. Korphage Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: M.L. Korphage 3/24/2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 26 2010
KCC WICHITA



Suite 700 • 155 North Market • Wichita, Kansas 67202-1821
(316) 262-3573

March 24 2010

Kansas Corporation Commission
Conservation Division
130 S. Market, Room 2078
Wichita, KS 67202-3802

Re: Well Plugging Record (Form CP-4)
Parkin "C" #1
SE-NE 7-30-18W
API# 15-097-20036-00-00
Kiowa Co., Kansas

KCC Staff:

Enclosed is a completed and signed Well Plugging Record (CP-4 form) for the above referenced well. Also attached is a copy of the cementing ticket which documents those completed plugging operations.

Should you have any questions or need additional information with regard to this filing, please contact me at the above letterhead address or telephone number.

Sincerely,

M.L. Korphage, P.G.
Geologist
Vincent Oil Corporation

XC: File

RECEIVED
MAR 26 2010
KCC WICHITA

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 3995

Date	2-18-10	Sec.	7	Twp.	30	Range	18	County	Kiowa	State	Ks	On Location		Finish	2:00
------	---------	------	---	------	----	-------	----	--------	-------	-------	----	-------------	--	--------	------

Lease	Parkin C	Well No.	1	Location	
-------	----------	----------	---	----------	--

Contractor	Quality Well Service	Owner	
------------	----------------------	-------	--

Type Job	PTA	To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.	
----------	-----	--	--

Hole Size		T.D.	
-----------	--	------	--

Csg.	4 1/2	Depth		Charge To	Vincent Oil Corp.
------	-------	-------	--	-----------	-------------------

Tbg. Size		Depth		Street	
-----------	--	-------	--	--------	--

Tool		Depth		City		State	
------	--	-------	--	------	--	-------	--

Cement Left in Csg.		Shoe Joint		The above was done to satisfaction and supervision of owner agent or contractor.		
---------------------	--	------------	--	--	--	--

Meas Line		Displace		CEMENT 15gcl on side.		
-----------	--	----------	--	-----------------------	--	--

EQUIPMENT				Amount Ordered	150sx	100/40	4%
Pumptrk	6	No.	Cementer	David			
			Helper				
Bulktrk	4	No.	Driver	Rich			
			Driver				
Bulktrk		No.	Driver	Terome			
			Driver				

JOB SERVICES & REMARKS				Calcium	1sx
------------------------	--	--	--	---------	-----

Remarks:		Hulls	400 #
----------	--	-------	-------

2-17-10 pumped 30SKS 200 # Hulls.		Salt	
-----------------------------------	--	------	--

displaced with 74bbbls water.		Flowseal	
-------------------------------	--	----------	--

2-18-10		Handling	
---------	--	----------	--

1st pumped 15gcl 50SKS 3%CC 100# Hulls		Mileage	45
--	--	---------	----

@ 1180'			
---------	--	--	--

2nd pumped 50SKS 100# Hulls @ 450'			
------------------------------------	--	--	--

		FLOAT EQUIPMENT	
--	--	-----------------	--

3rd pumped 20SKS @ 40' to surface		Guide Shoe	
-----------------------------------	--	------------	--

		Centralizer	
--	--	-------------	--

		Baskets	
--	--	---------	--

		AFU Inserts	
--	--	-------------	--

		4 1/2 wiper plug	
--	--	------------------	--

--	--	--	--

--	--	--	--

		Pumptrk Charge	
--	--	----------------	--

		Mileage	
--	--	---------	--

--	--	--	--

--	--	--	--

X Signature	David Brady		
-------------	-------------	--	--

RECEIVED
MAR 26 2010
KCC WICHITA