

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 9067
Name: DaMar Resources, Inc.
Address 1: 234 W. 11th St.
Address 2: P. O. Box 70
City: Hays State: KS Zip: 67601 +
Contact Person: Curtis R. Longpine
Phone: (785) 625-0020
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-02635-0000
Spot Description: _____
C. NW, NE, NE Sec. 30 Twp. 13 S. R. 16 East West
330 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Theodore Gore Well #: 3
Date Well Completed: 1/2/64
The plugging proposal was approved on: _____ (Date)
by: Pat Staab (KCC District Agent's Name)
Plugging Commenced: 1/9/10
Plugging Completed: 1/11/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	10 3/4"	1118'	none
		Production	5 1/2"	3491'	1925'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

See enclosed plugging report

Plugging Contractor License #: 6426 Name: Express Well Service
Address 1: P. O. Box 19 Address 2: _____
City: Victoria State: KS Zip: 67671 + 0019
Phone: (785) 735-9405
Name of Party Responsible for Plugging Fees: DaMar Resources, Inc.
State of Kansas County, Ellis, ss.
Curtis R. Longpine Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 25 2010
3-25-10
CONSERVATION DIVISION
WICHITA, KS

**DaMar Resources Inc
T Gore #3
Ellis Co Ks.**

1-8-10

Schmidtberger Cont dug out well head. Weld Teck took off ring and cut off packing nut.

1-9-10

Rigged up Express Well Service, Picked up 5 ½ out of head. Moved casing 10 ½ ' from slack off to 40th .

1-11-10

Rigged up LK and Free pointed pipe at 1950. Set CIBP at 3150' Topped w/ 5 sxs cement. Put 15 bbls water in casing. Cut off pip-e at 1925. Pulled to 1835 and Rigged up Quality Cement and pumped 130 sxs 60/40 w/ 4% gel and 300# hulls. Pulled pipe to 1'114 and pumped 19 sxs gel and 30 sxs cement. Pulled to 624 and filled hole to surface w/ 150 sxs and 200# hulls. Pulled all casing and topped of 10 ¾ w/ 25 sxs. Hauled off water. RD

Note 5 ½ pipe looked good to 1150, and bad for 3 jts then good again. 57 jts.

Will cut off and fill cellar and pit.

KCC rep Pat Staab

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 25 2010

CONSERVATION DIVISION
WICHITA, KS