

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 9067  
Name: DaMar Resources, Inc.  
Address 1: 234 W. 11th St.  
Address 2: P. O. Box 70  
City: Hays State: KS Zip: 67601 +  
Contact Person: Curtis R. Longpine  
Phone: (785) 625-0020  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 051-25920-0000  
Spot Description: \_\_\_\_\_  
NE SW SE Sec. 21 Twp. 13 S. R. 16  East  West  
410 Feet from  North /  South Line of Section  
2,010 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ellis  
Lease Name: Karin Family Well #: 1  
Date Well Completed: 12/23/09  
The plugging proposal was approved on: 1/12/10 (Date)  
by: Pat Staab (KCC District Agent's Name)  
Plugging Commenced: 1/12/10  
Plugging Completed: 1/12/10

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		surface	8 5/8"	220'	0
		production	5 1/2"	3557	2300

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

See enclosed plugging report

Plugging Contractor License #: ~~9067~~ 99977 Name: DaMar Resources, Inc.  
Address 1: P. O. Box 70 Address 2: 234 W. 11th St.  
City: Hays State: KS Zip: 67601 + DK  
Phone: (785) 625-0020  
Name of Party Responsible for Plugging Fees: Quality Oilwell Cementing, Inc.  
State of Kansas County, Ellis, ss.  
Curtis R. Longpine  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
MAR 19 2010  
3-19-10  
KCC WICHITA

Karlin Family # 1 Page 2

1-12-10

Rigged up Express Well Service. Rigged up LK and set CIBP at 3150 and dumped 5 sxs cement on plug. Pulled slips and Shot off pipe at 2300'

Pulled to 1115 50 sxs w/ 200 # Hulls Pulled to 573 and pumped cement to surface w/ 140 sxs. Pulled remaining casing. Topped off 8 5/8 w/ 30 sxs.

All cement 160/40 w/ 4% gel.

Pulled 54 jts long pipe and 2 short jts.

KCC rep Pat Staab.