

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33168
Name: Woolsey Operating Company, LLC
Address 1: 125 N. Market, Suite 1000
Address 2: _____
City: Wichita State: KS Zip: 67202 + _____
Contact Person: Carl W. Durr
Phone: (620) 886-5606 Ext. 27
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-033-20523-00-01
Spot Description: SE NW
NE SW SE NW Sec. 33 Twp. 34 S. R. 16 East West
1980 2080 Feet from North / South Line of Section
1980 1750 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Comanche
Lease Name: Oller Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 02/09/10
Plugging Completed: 02/11/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8 5/8"	421'	
			4 1/2"	5,728'	4,050'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand was at 5,150'. Bailed 4 sacks cement with bailer. Ripped casing at 4,050'; Pulled casing up to 880'. Pumped 12 gel 50 sacks 3% cc 100# hulls at 880'. Pulled to 450'; Pumped 50 sacks 100# hulls. Pulled to 40'; Pumped 20 sacks to surface. Topped off well with 10 sacks.

RECEIVED

MAR 01 2010

KCC WICHITA

Plugging Contractor License #: 31925 Name: Quality Well Service
Address 1: 190th US 56 Highway Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410
Name of Party Responsible for Plugging Fees: Woolsey Operating, LLC
State of Ks County, Barber, ss.
Carl W Durr Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Carl W Durr