

KANSAS CORPORATION COMMISSION
 OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
 Please TYPE Form and File ONE Copy

Form CP-1
 March 2009
 This Form must be Typed
 Form must be Signed
 All blanks must be Filled

OPERATOR: License #: 33168
 Name: Woolsey Operating Company, LLC
 Address 1: 125 N Market, Suite 1000
 Address 2: _____
 City: Wichita State: Ks Zip: 67202 + _____
 Contact Person: Carl W. Durr
 Phone: (620) 886-5606 #27

API No. 15 - 007-23180-0000
 If pre 1967, supply original completion date: _____
 Spot Description: 200' N
NW - SE NW Sec. 11 Twp. 34 S. R. 12 East West
1.450 Feet from North / South Line of Section
1.650 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Barber
 Lease Name: Farney Trust Well #: 1

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
 Surface Casing Size: 10 3/4" Set at: 214' Cemented with: 200 Sacks
 Production Casing Size: 4 1/2" Set at: 5103' Cemented with: 210 Sacks

List (ALL) Perforations and Bridge Plug Sets:
4690' to 4700', 4716' to 4740' & 4744' to 4762'

pipe recy 3430

Elevation: 1480' (G.L. / K.B.) T.D.: 5250' P.B.T.D.: 5072' Anhydrite Depth: N/A
(Stone Coral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____

Proposed Method of Plugging (attach a separate page if additional space is needed):
As per KCC recommendation.

(interval)
 Bottom 3 Sand to 4640 + 45x cmt.
 or Pump w/ 300# hulls + 205x cmt.
 1st plug @ 600' w/ 105x + 50 cmt
 2nd plug @ 240' w/ ~~105x~~ 175x cmt.
 3rd plug @ 40' w/ 305x cmt. SP 21310

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No
 If ACO-1 not filed, explain why: _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Carl W. Durr
 Address: P.O. Box 168 City: Medicine Lodge State: Ks Zip: 67104 + _____
 Phone: (620) 886-5606 #27
 Plugging Contractor License #: 31925 Name: Quality Well Service
 Address 1: 190 US Hwy 56 Address 2: _____
 City: Ellinwood State: Ks Zip: 67526 + _____
 Phone: (620) 727-3409
 Proposed Date of Plugging (if known): 2/5/10

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
 Date: 2/3/2010 Authorized Operator / Agent: Carl W. Durr
(Signature)

RECEIVED
 MAR 01 2010
 KCC WICHITA

Quality Well Service, Inc.

190 US Highway 56
Ellinwood, KS 67526

Invoice

Date	Invoice #
2/22/2010	1154

Bill To
Woolsey Operating Company LLC 125 N Market, #1000 Wichita, KS 67202

P.O. No.	Terms	Lease Name
	Net	Farney Trust #1

Description	Qty	Rate	Amount
Rig Time	22	185.00	4,070.00T
Floor Rental	1	125.00	125.00T
Sand	1	35.00	35.00T
Cement	4	9.00	36.00T
Shots	2	300.00	600.00T
Water Truck	5.5	75.00	412.50T
Backhoe	5	75.00	375.00T
Out of Town	2	120.00	240.00T
Phone Calls	1	15.00	15.00T
Clerical	1	20.00	20.00T
Wiping Rubber	1	20.00	20.00T
Fresh Water	1	20.00	20.00T
02/03/10: Drove to location and raised pole. Checked hole; Sanded off bottom. Loaded hole with water. Took fence down around pumping. Drove to motel.			
02/08/10: Drove to location; Checked hole; Sand was at 4,640'. Bailed 4 sacks cement with bailer. Dug cellar; unpacked casing head. Set floor; Pulled slips. Ripped casing at 3,610' and 3,430'. Pipe came free. Started pulling casing; Well started flowing oil; Pumped 20 bbls water down 4 1/2". Finished pulling casing to 600'; Swedge in. Drove to motel.			
		Subtotal	
		Sales Tax (6.3%)	
		Total	

RECEIVED
MAR 01 2010

Quality Well Service, Inc.

**190 US Highway 56
Ellinwood, KS 67526**

Invoice

Date	Invoice #
2/22/2010	1154

Bill To
Woolsey Operating Company LLC 125 N Market, #1000 Wichita, KS 67202

P.O. No.	Terms	Lease Name
	Net	Forney Trust #1

Description	Qty	Rate	Amount
02/09/10: Drove to location. Pumped 10 gell 50 sacks 3% CC 100# hulls at 600'. Pulled to 240'; Pumped 75 sacks 100# hulls. Pulled to 40'; Pumped 30 sacks to surface. Tore down floor and rig. Emptied pit. Cleaned up location.			

**RECEIVED
MAR 01 2010
KCC WICHITA**

Subtotal	\$5,968.50
Sales Tax (6.3%)	\$376.02
Total	\$6,344.52