

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5004  
Name: Vincent Oil Corporation  
Address 1: 155 N. Market, Ste 700  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67202 + 1821  
Contact Person: M.L. Korphage  
Phone: (316) 262-3573  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 3770  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 113-21336-00-00  
Spot Description: SE-NW-NE-NE 4  
SE NW-NE-NE Sec. 23 Twp. 18 S. R. 3  East  West  
607 Feet from  North /  South Line of Section  
834 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: McPherson  
Lease Name: Goering Well #: 1-23  
Date Well Completed: 1/6/2010  
The plugging proposal was approved on: 1/4/2010 (Date)  
by: Virgil Clothier (KCC District Agent's Name)  
Plugging Commenced: 1/05/2010  
Plugging Completed: 1/06/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Conductor	13 3/8"	208'	None
		Surface pipe	8 5/8"	560'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hole filled with heavy drilling mud with cement plugs spotted through drill pipe as follows:  
1st Plug: 35 sx at 3728', 2nd Plug: 35 sx at 610', 3rd Plug: 35 sx at 400', Top Plug: 25 sx at 60' to surface. Plugged rathole with 15 sx and mousehole with 10 sx; Plug Down at 3:30 AM 1/6/2010. Used a total of 155 sx 60 / 40 Poz (4% Gel & 1/4 # flo-seal / sx). Allied Cementing LLC Ticket # 036196

Plugging Contractor License #: 4958 Name: Mallard JV Inc.  
Address 1: P.O. Box 1009 Address 2: \_\_\_\_\_  
City: McPherson State: Kansas Zip: 67460 + 1009  
Phone: (620) 241-4640  
Name of Party Responsible for Plugging Fees: Vincent Oil Corporation  
State of Kansas County, Sedgwick, ss.  
M.L. Korphage  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed the same are true and correct, so help me God.

Signature: M.L. Korphage

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 22 2010  
4-22-10  
CONSERVATION DIVISION  
WICHITA, KS