

MAR 05 2010

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34055 Name: H & M Petroleum Corporation Address 1: 13570 Meadowgrass Dr Ste 101 Address 2: City: Colorado Springs State: CO Zip: 80921 Contact Person: David Allen Phone: (719) 590-6060 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Depth to Top: Bottom: T.D.

API No. 15 - 065-23614-00-00 Spot Description: NW SE SW NW Sec. 3 Twp. 9 S. R. 25 East West 2.143 Feet from North South Line of Section 725 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Graham Lease Name: Oil Creek Well #: 2 Date Well Completed: 2/2/10 The plugging proposal was approved on: 2/1/10 (Date) by: Marvin Mills (KCC District Agent's Name) Plugging Commenced: 2/3/10 @ 5:00 pm Plugging Completed: 2/3/10 @ 7:30 pm

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Surface, 8 5/8, 220, None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Commenced Cementing 2/3/10 @ 5:00 pm. 1st plug: 25sx @ 2190', 2nd plug: 100sx @ 1805', 3rd plug: 40sx @ 270', 4th plug: 10sx @ 40', 30sx in the rathole. A total of 205sx of 60/40 poz - 4% gel - 1/4# per sx flo-seal. Completed cementing 2/3/10 @ 7:30 pm, by SOS Cementing.

Plugging Contractor License #: 33575 Name: WW Drilling, LLC Address 1: 233 S 4th Address 2: PO Box 307 City: Wakeeney State: KS Zip: 67672 Phone: (785) 743-6774

Name of Party Responsible for Plugging Fees: H & M Petroleum Corporation State of Colorado County: EL PASO, ss. David Allen (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: David J. Allen