

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 32278  
Name: Tengasco, Inc.  
Address 1: P.O. Box 458  
Address 2: \_\_\_\_\_  
City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Contact Person: Gary Wagner  
Phone: ( 785 ) 625-6374  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 009-24,578 00 00  
Spot Description: \_\_\_\_\_  
NE NE NW Sec. 19 Twp. 20 S. R. 15  East  West  
330 Feet from  North /  South Line of Section  
2,310 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barton  
Lease Name: Iannitti Well #: 8  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 01/26/2010 (Date)  
by: Case Morris (KCC District Agent's Name)  
Plugging Commenced: 02/25/2010  
Plugging Completed: 02/26/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	1149'	0'
		Production	5-1/2"	3881'	1630.74'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

02/25/10 - Drove to location. Rigged up. Ran sand line & tagged sand @ 3750'. Bailed 5 sacks cement on top of sand. Rigged jacks up. Pulled stretch - had 7-1/2".  
02/26/10 - Drove to location. Shot casing @ 2002' - did not come loose. Shot casing @ 1620' - casing loose. Spotted 125 sacks 60/40 4% gel w/300# Hulls @ 1600'. Spotted 50 sacks 60/40 4% gel w/100# Hulls @ 700'. Pulled casing to 150' & circulated cement to surface w/50 sacks 60/40 4% gel. Pull casing - hole full. R.D.M.O.  
\*Pulled 46 joints 5-1/2" casing - 1630.74'.  
State Man on location - Bruce Rodie

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc.  
Address 1: 1822 24th Street Address 2: \_\_\_\_\_  
City: Great Bend State: Kansas Zip: 67530 + \_\_\_\_\_  
Phone: ( 620 ) 793-5838  
Name of Party Responsible for Plugging Fees: Tengasco, Inc.  
State of Kansas County, Barton, ss.  
Tim Dickson  Employee of Operator or  Operator on above-described well.  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tim Dickson

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MAR 11 2010

KCC WICHITA