

15-063-30094-00-00

FORM - CP-2
Rev. 9-8-64

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
OCT 7 1964
10-05-66
CONSERVATION DIVISION
STATE OF KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Co., has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 4th Nat'l Bank Bldg., Wichita, Kansas.

Lease Name: Rohr Well No. B-2

Location: CSE-NW Sec. 34 Twp. 14 Rge. (E)(W) 27

County Gove Total Depth 3710 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Burton was instructed to plug the well as follows:

247'--8 5/8" Surface pipe, cement circulated with 165 Sx.
Twisted off Drill pipe, unable to fish--hole abandoned.

Circulate hole with heavy mud, set plug @ 500' and 25 Sx. cement.

" " " 240' and 20 Sx. cement.

" " " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

W. L. Nichols
Conservation Division Agent