

15-167-04981-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 11-2

LOCATION SE SE SW

SEC. 8 TWP. 14 RGE. 12

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Mahoney

Operator Pinsker Supply Co Address Wichita, Kans

Field _____ County Russell

Total Depth 2979 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 150' circulated with cement; 5 1/2" at 2960'

Filled with sand to 2950', set 5vsax cement with dump bailer,

pulled 1815' 5 1/2" casing, mudded hole to 150', set wood plug,

rock and 15 sax cement, mudded hole to 35', set rock bridge

and 10 sax cement to bottom cellar.

07-10-1950

Edwin L. ...
District Conservation Agent

Date 7-6-50

PLUGGING
FILE SEC 8 TWP 14 RGE 12
BOOK PAGE 11 LINE 8