

State of Kansas



15-167-20386-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1970 01-13-70
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Ensminger of American Drilling Company has this date requested permission to plug the following described well:

Mr. F. W. Vishnefike guarantees payment of the plugging fee.

Operator's full Name: Saline Basin Petroleum Company

Complete Address: 119 S. Santa Fe, Salina, Kansas

Lease Name: Klein Well No. # 1-B

Location: SE SE NW Sec. 16 Twp. 14 Rge. 11 (E)(W) W

County: Russell Total Depth 2969 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Jack Ensminger was instructed to plug the well as follows:

8 5/8" 268' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 45 sax
cement thru drill pipe. Mud to 260' & displaced 25 sax cement thru drill
pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with
Allied Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

[Signature]
Conservation Division Agent